

Accept

Decline

Date: Sep 8, 2022

No. 1286

Estimate

Anew Contractors

312 Farabee Dr S
Lafayette, IN 47905
(765) 250-4603 Office
www.anewcontractors.com
Josh@anewcontractors.com



Presented To:

Village of Orland Park
14671 West Avenue
Orland Park, IL 60462

Description of Service	Amount
Building Washing: Cabin #2 - Wash and prep the exterior of the structure.	\$1,823.00
Chinking: Cabin #2- Remove all existing chinking. Tarps will be placed on the ground during this process. All debris will be disposed of in the onsite dumpster. Between each log will be inspected. Any rot will be addressed with M-Balm epoxy. Grip strip will be custom cut to fit between each log course. Light Gray Perma-Chink will be pumped into each joint and tooled by hand. Chinking finish will appear similar to the time period and what it currently on the home.	\$17,864.00
Log Repair: Cabin #2- Base log at the front of the home. Remove all rot. Clean the area and treat with borates. Reface the log using a recovered barn beams. Replacement beam will be treated with borates prior to moving onsite.	\$3,227.00
Staining: Cabin #2 - All Exterior wood surfaces including doors, fascia, soffits, and logs. Application of borates to all wood surfaces. Application Prelude primer to all surfaces listed. Application of Log end seal to each log end. Stain all surfaces with Lifeline Ultra-7 in the Rustic Gray#372 color. Application of Lifeline Advanced Satin with Bug Juice insecticide to all exterior surfaces.	\$6,853.00

Total \$29,767.00

Thank you for allowing us the opportunity to present our service to you!