



SALES QUOTATION

QUOTE NO.	ACCOUNT NO.	DATE
CRLJ365	0763376	4/24/2012

BILL TO:
VILLAGE OF ORLAND PARK
14700 S RAVINIA AVE

SHIP TO:
VILLAGE OF ORLAND PARK
Attention To: NORM JOHNSON
14700 S RAVINIA AVE

Accounts Payable
ORLAND PARK , IL 60462-3167

ORLAND PARK , IL 60462-3167
Contact: NORM
JOHNSON 708.403.6210

Customer Phone #708.403.6100

Customer P.O. # TRIPPLITE OPTION

ACCOUNT MANAGER		SHIPPING METHOD	TERMS	EXEMPTION CERTIFICATE
PHILIPPE STAPP 866.551.9995		NITE MOVES MESSENGER	Net 30 Days-Govt State/Local	E9998-1807-05
QTY	ITEM NO.	DESCRIPTION	UNIT PRICE	EXTENDED PRICE
4	1702988	TRIPP 3000VA UPS SMART ONLINE 2U RM Mfg#: SU3000RTXL2U Contract: National IPA Technology Solutions 083052-01	1,164.29	4,657.16
4	309803	TRIPP SW SNMP/WEB MGMT ACCESSO Mfg#: SNMPWEBCARD Contract: National IPA Technology Solutions 083052-01	220.21	880.84
SUBTOTAL				5,538.00
FREIGHT				0.00
TAX				0.00
				US Currency
TOTAL				5,538.00

CDW Government
230 North Milwaukee Ave.
Vernon Hills, IL 60061
Phone: 847.371.5000

Fax: 312.752.3630

Please remit payment to:
CDW Government
75 Remittance Drive
Suite 1515
Chicago, IL 60675-1515



Quantity 1 - Generac industrial gas engine driven generator, naturally aspirated 4.2L V-6 engine, consisting of the following features and accessories: SG0035GG034.2N18HPSYA

- Natural gas - 35 kW Rating , synchronous alternator, wired for 120/208 VAC 3 Phase, 60 HZ
- Permanent magnet excitation
- H-100 Control Panel
 - o Meets NFPA 99 and 110 requirements
 - o Temp Range -40 to 70 degrees C
 - o Digital microprocessor:
 - Two 4 line x 20 displays, full system status
 - 3 phase sensing, +/-0.25% digital voltage regulation
 - RS232, RS485 and Canbus remote ports
 - Waterproof connections
 - All engine sensors are 4-20 ma for minimal interference
 - Programmable I/O
 - Built-in PLC for special applications
 - o Engine function monitoring and control:
 - Full range standby operation; Programmable auto crank, Emergency Stop, Auto-Off-Manual switch
 - Isochronous governor, +/-0.25% frequency regulation
 - Full system status on all AC output and engine function parameters
 - Service reminders, trending, fault history (alarm log)
 - I2T function for full generator protection
 - Selectable low-speed exercise
 - o HTS transfer switch function monitoring and control
 - o 2-wire start controls for any 2-wire transfer switch
- Electronic governor Frequency regulation, isochronous Steady state regulation +/-0.25%
- 100A UL mainline circuit breaker – 100% Rated
- **Sound attenuated, weather protective enclosure**
 - o Industrial Grey enclosure, powder paint finish
 - o Integral critical grade muffler
- 110AH, 925 CCA, group 31 - battery w/rack-installed, 10AMP battery charger-installed
- Battery charging alternator, Battery cables, Battery tray
- Fuel shut-off solenoid valve
- Solenoid activated starter motor
- Air cleaner and oil filter with internal bypass
- Oil and antifreeze, Oil and radiator drain extensions
- Vibration isolators between engine/alternator and base frame
- Standard flex exhaust
- Block Heater 1500W 120VAC
- Engine run relay
- Alternator strip heater
- 21 Light annunciator with 8 function relay - surface mount
- Pad type vibration isolators
- Standard set of 3 manuals
- UL Listed for USA & Canada
- 5 year extended warranty

Quantity 1 -One automatic transfer switch consisting of the following typecode and components:

- GTS010W-3G2LDNAN
- **100 amps, 3 Pole constructionOperating at 60 HZ, 208 Volts 3 phase, with 2-wire start circuit**
- Utility voltage sensing controls: * Drop-out and pick-up * Utility interrupt delay
- Adjustable logic controls * Minimum standby voltage * Minimum standby frequency * Engine warmup * Inphase monitor * Time delay neutral * Return to utility * Engine cooldown * Transfer on exercise
- NEMA 1 Enclosure
- Standard set of 3 manuals
- UL 1008 listed
- CSA Certified
- Standard 2 Year warranty

Start-Up Included during normal business hours 8AM-5PM

Freight Included

Total for Generator, ATS and Field Services (Not including any applicable tax), With National IPA Participating Agency #15276 Applied: \$25,427.75

Installation

We will provide labor and materials to:

Install and wire SG035 natural gas generator in grass area outside West of IT Room, as follows:

- Furnish and install concrete pad 3' from building.
- Furnish and install gas piping and connections from existing gas line in Hall outside Boiler Room.
- Install a new 100 Amp ATS in electrical closet on 1st Floor.
- Relocate A/C power from basement panel to 1st Floor panel.
- Furnish and install all wiring from generator to ATS and power and control.
- All work during normal business hours, except final connections at ATS. Saturday OT is included.
- Generator to have a 100 Amp 100% rates main breaker. ATS to be 100 Amp 120/200 3-phase 4 w.

The price for the above described work With NIPA Participating Agency #15276 is \$27,502.50

Installation performed by Union Electricians – Therm Flo, Inc. 251 Holbrook Drive Wheeling, IL 60090

Estimated Delivery: 6-8 Weeks

Prices valid for 90 days from above date

FOB Factory, freight allowed to first destination only (unload off truck and rigging by others)