

CLERK'S CONTRACT and AGREEMENT COVER PAGE

Legistar File ID#: 2016-0162

Innoprise Contract #: C16-0038

Year: 2016

Amount: \$4,167,852.68

Department: Rich Rittenbacher - PW

Contract Type: Construction

Contractors Name: D Construction, Inc.

Contract Description: Road Improvement Program 2016
C16-0079 Addendum A Kristo Lane & Dorstep Lane (2016-0396/399
\$75,338.38)

**ADDENDUM A to
Road Improvement Program 2016**

**Dated
March 22, 2016**

Between

The Village of Orland Park, Illinois ("VILLAGE") and D. Construction, Inc. ("CONTRACTOR")



WHEREAS, on 22nd day of March, 2016, a certain Agreement regarding Road Improvement Program 2016 between the Village and the Contractor was executed (hereinafter referred to as the "Agreement"); and,

WHEREAS, the Village wishes to modify the SCOPE OF WORK.

NOW, THEREFORE, for and in consideration of the foregoing and the mutual covenants herein contained, it is agreed by and between the parties hereto as follows:

1. In the event of any conflict or inconsistency between the provisions of this Addendum and the Agreement, the provisions of this Addendum shall control.
2. **SECTION 1: THE CONTRACT DOCUMENTS** of said Agreement shall be amended to include Addendum A dated July 1, 2016
3. **SECTION 2: SCOPE OF THE WORK AND PAYMENT** of said Agreement shall be amended to include the following before the words "10% retention..."

"Per Addendum A dated July 1, 2016, the resurfacing of Kristo Lane, and Dorstep Lane/81st Avenue as outlined in the Construction Estimate at a cost of Seventy Five Thousand Three Hundred Thirty-Eight and 38/100 (\$75,338.38) Dollars. Additionally, the scope shall include the installation of sidewalk and pedestrian path gaps at the stated unit prices, for a total amount not to exceed Board approved budgeted dollars."

4. All of the other terms, covenants, representations and conditions of said Agreement not deleted or amended herein shall remain in full force and effect during the effective term of said Agreement.
5. This Addendum may be executed in two or more counterparts, each of which taken together, shall constitute one and the same instrument.

ADDENDUM A to
Road Improvement Program 2016

Dated
March 22, 2016

Between
The Village of Orland Park, Illinois ("VILLAGE") and D. Construction, Inc. ("CONTRACTOR")

This Addendum, made and entered into effective the **1st day of July, 2016**, shall be attached to and form a part of the Agreement dated the 22nd day of March, 2016 and shall take effect upon signature below by duly authorized agents of both parties.

AGREED AND ACCEPTED

FOR: THE VILLAGE

By: Timothy J. McCarthy
Print Name: TIMOTHY J. MCCARTHY
Its: INTERIM VILLAGE MANAGER
Date: August 17, 2016

FOR: THE CONTRACTOR

By: [Signature]
Print Name: Kenneth Sandeno
Its: President
Date: August 8, 2016

Kristo Lane & Dorstep Lane Construction Cost Estimate

						Overall Total		Kristo Lane 480 L.F. 1440 S.Y.		Dorstep Lane 860 L.F. 2580 S.Y.	
No.	IDOT	Item	Quantity	Unit	Unit Price	Amount					
1	42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	120	SQ FT	\$4.75	\$570.00	120	\$570.00	0	\$0.00	
2	42400800*	DETECTABLE WARNINGS	20	SQ FT	\$31.50	\$630.00	20	\$630.00	0	\$0.00	
3	44000600	SIDEWALK REMOVAL	0	SQ FT	\$1.00	\$0.00	0	\$0.00	0	\$0.00	
4	60608300	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-2.12	242	FOOT	\$18.25	\$4,416.50	65	\$1,186.25	177	\$3,230.25	
5	60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	0	FOOT	\$20.50	\$0.00	0	\$0.00	0	\$0.00	
6	44000500	COMBINATION CURB AND GUTTER REMOVAL	242	FOOT	\$4.25	\$1,028.50	65	\$276.25	177	\$752.25	
7	*	CONCRETE SLAB RAISING	0	SQ FT	\$2.25	\$0.00	0	\$0.00	0	\$0.00	
8	XX006395*	SHOTCRETE CURB & GUTTER REPAIR	40	FOOT	\$35.00	\$1,400.00	20	\$700.00	20	\$700.00	
9	*	P.C.C. DRIVEWAY REMOVAL & REPLACEMENT, 5"	0	SQ FT	\$5.50	\$0.00	0	\$0.00	0	\$0.00	
10	*	H.M.A. DRIVEWAY REMOVAL & REPLACEMENT, 3"	0	SQ YD	\$39.00	\$0.00	0	\$0.00	0	\$0.00	
11	*	BRICK DRIVEWAY REMOVAL & REPLACEMENT	40	SQ FT	\$15.00	\$600.00	0	\$0.00	40	\$600.00	
12	*	IMPRINTED COLORED PCC DRIVEWAY REMOVAL & REPLACEMENT	0	SQ FT	\$11.00	\$0.00	0	\$0.00	0	\$0.00	
13	*	IMPRINTED COLORED HMA DRIVEWAY REMOVAL & REPLACEMENT	0	SQ YD	\$150.00	\$0.00	0	\$0.00	0	\$0.00	
14	X0326806*	WASHOUT BASIN	1	EACH	\$400.00	\$400.00	0.5	\$200.00	0.5	\$200.00	
15	20200100*	EARTH EXCAVATION	5	CU YD	\$20.00	\$100.00	5	\$100.00	0	\$0.00	
16	44000167	HOT-MIX ASPHALT SURFACE REMOVAL, 4 1/2"	0	SQ YD	\$2.50	\$0.00	0	\$0.00	0	\$0.00	
17	44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 1 3/4"	0	SQ YD	\$1.40	\$0.00	0	\$0.00	0	\$0.00	
18	40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	40	SQ YD	\$0.01	\$0.40	40	\$0.40	0	\$0.00	
19		HOT-MIX ASPHALT SURFACE REMOVAL, EDGE MILL	8,100	SQ YD	\$1.75	\$14,175.00	6750	\$11,812.50	1350	\$2,362.50	
20	40600100	HOT-MIX ASPHALT - PRIME COAT (BDE)	410	GALLON	\$0.01	\$4.10	150	\$1.50	260	\$2.60	
21	*	CLASS D PATCHES- VARIOUS TYPES	150	TON	\$80.00	\$12,000.00	30	\$2,400.00	120	\$9,600.00	
22	*	CLASS D PATCHES- VARIOUS TYPES- OFFSITE	0	TON	\$142.00	\$0.00	0	\$0.00	0	\$0.00	
23	35101400*	AGGREGATE BASE COURSE, TYPE B	0	TON	\$13.00	\$0.00	0	\$0.00	0	\$0.00	
24	35800100	PREPARATION OF BASE	0	SQ YD	\$0.85	\$0.00	0	\$0.00	0	\$0.00	
25	35800200	AGGREGATE BASE REPAIR	0	TON	\$20.00	\$0.00	0	\$0.00	0	\$0.00	
26	40201000*	AGGREGATE FOR TEMPORARY ACCESS	0	TON	\$17.00	\$0.00	0	\$0.00	0	\$0.00	
27	20800150*	TRENCH BACKFILL, CA-6	10	TON	\$18.00	\$180.00	0	\$0.00	10	\$180.00	
28	20800150*	TRENCH BACKFILL, CA-7	10	TON	\$24.00	\$240.00	0	\$0.00	10	\$240.00	
29	40600825	POLYMERIZED LEVELING BINDER (MACHINE METHOD), N50	200	TON	\$79.00	\$15,800.00	70	\$5,530.00	130	\$10,270.00	
30	40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	0	TON	\$53.73	\$0.00	0	\$0.00	0	\$0.00	
31	40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	355	TON	\$57.50	\$20,412.50	130	\$7,475.00	225	\$12,937.50	
32	25000110*	SEEDING, CLASS 1A (& TOPSOIL)	20	SQ YD	\$4.20	\$84.00	5	\$21.00	15	\$63.00	
33	25100630	EROSION CONTROL BLANKET	20	SQ YD	\$5.25	\$105.00	5	\$26.25	15	\$78.75	
34	25200100*	SODDING (& TOPSOIL)	0	SQ YD	\$18.00	\$0.00	0	\$0.00	0	\$0.00	
35	28000510	INLET FILTERS	4	EACH	\$0.01	\$0.04	2	\$0.02	2	\$0.02	
36	60109520*	PIPE UNDERDRAINS FABRIC LINED TRENCH, 6"	150	FOOT	\$16.00	\$2,400.00	0	\$0.00	150	\$2,400.00	
37	550B0330*	STORM SEWERS, CLASS B, TYPE 2 10"	0	FOOT	\$30.00	\$0.00	0	\$0.00	0	\$0.00	
38	60207005*	CATCH BASINS, TYPE C, FRAME & LID	0	EACH	\$1,675.00	\$0.00	0	\$0.00	0	\$0.00	
39	60300305*	FRAMES AND LIDS TO BE ADJUSTED (STEEL RING)	0	EACH	\$150.00	\$0.00	0	\$0.00	0	\$0.00	
40	60255500*	MANHOLES TO BE ADJUSTED	1	EACH	\$280.00	\$280.00	0	\$0.00	1	\$280.00	
41	60257900*	MANHOLES TO BE RECONSTRUCTED, BLOCK	0	EACH	\$900.00	\$0.00	0	\$0.00	0	\$0.00	
42	60257900*	MANHOLES TO BE RECONSTRUCTED, CONE SECTION	0	EACH	\$900.00	\$0.00	0	\$0.00	0	\$0.00	
43	60257900*	MANHOLES TO BE RECONSTRUCTED, FLAT SLAB TOP	0	EACH	\$1,000.00	\$0.00	0	\$0.00	0	\$0.00	
44	*	MANHOLE TO BE MORTARED	4	EACH	\$65.00	\$260.00	1	\$65.00	3	\$195.00	
45	88600100	DETECTOR LOOP, TYPE I	0	FOOT	\$20.00	\$0.00	0	\$0.00	0	\$0.00	
46	*	TRAFFIC CONTROL AND PROTECTION, SPECIAL	0	LSUM	\$35,000.00	\$0.00	0	\$0.00	0	\$0.00	
47	78000100	THERMOPLASTIC PAVEMENT MARKING- LETTERS & SYMBOLS	0	SQ FT	\$6.80	\$0.00	0	\$0.00	0	\$0.00	
48	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	0	FOOT	\$0.66	\$0.00	0	\$0.00	0	\$0.00	
49	78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	54	FOOT	\$0.91	\$49.14	54	\$49.14	0	\$0.00	
50	78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	40	FOOT	\$2.00	\$80.00	40	\$80.00	0	\$0.00	
51	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	28	FOOT	\$4.40	\$123.20	28	\$123.20	0	\$0.00	

\$75,338.38

\$31,246.51

\$44,091.87