




- Notes:
- Rough grade to be within 1" of finished grade.
 - All existing and proposed landscape beds to be machine spade edged and mulched to a 3" depth with single processed hardwood mulch unless noted on plan
 - Trees not in landscape beds to be mulched with 6" diameter tree ring.
 - Plant material to be initially watered after installation by landscape contractor.
 - Contractor to call JULIE locate prior to work commencement
 - Any existing turf areas disturbed shall be repaired with all-purpose seed and blanket.
 - Sod to be premium bluegrass sod cut same day as installation and initially watered by contractor. Areas noted on plan
 - Metal edging to be 4" steel edging with 4 stakes per length

LEGEND

- Permeable pavers – See Detail L-3. D
- Machine Spade Edging
- Metal edging
- 1 1/2" river rock 2" depth with 20 yr. spun bound Landscape fabric (around foundation only)
- Trees to be Removed
- Mitigation Trees
- Existing Shade Tree
- Existing Ornamental Tree
- Existing Evergreen Tree
- Proposed Shade tree
- Proposed Ornamental tree
- Proposed Evergreen Tree

SITE DATA	
GROSS AREA	169,518 SF
LANDSCAPE AREA	52,939 SF
NUMBER OF REGULAR PARKING STALLS	199
HANDICAP STALLS	7
NO. OF PARKING ISLANDS	23
SQUARE FOOTAGE OF PARKING ISLANDS	10,641 S.F.
AREA OF PERMEABLE PAVERS	8418 S.F.

LANDSCAPE PLAN
Scale: 1"=20'-0"



ALLIED NURSERY

3197 S. CHICAGO ST. JOLIET, IL 61722-2280

DESIGNED AND DRAFTED BY: KRISTI SEITZ (R.L.A.)

LANDSCAPE PLAN

HAMPTON INN ORLAND PARK, IL

HAWKEYE HOTELS

160 SOUTHGATE AVE., SUITE A IOWA CITY, IOWA 52240

REVISIONS	DATE	REMARKS
NO.	DATE	REMARKS
0	9/28/2018	FOR CLIENT AND CITY REVIEW
1	10/10/2018	FOR CLIENT AND CITY REVIEW
2	11/16/2018	FOR CLIENT AND CITY REVIEW
3	1/26/2019	FOR CLIENT AND CITY REVIEW
4	3/1/2019	FOR FINAL APPROVAL
5	4/7/2019	REVISED PER SITE PLAN CHANGE

L-1

SHEET 1 OF 3