



Orland Park

Semmer Landscape LLC

Client Name: Gary Couch

Project Name: Retaining Wall Repair

Jobsite Address: 144th & 1st Avenue Orland Park, IL 60462

Billing Address: 14700 Ravinia Ave Orland Park, IL 60462

Estimate ID: EST664020

Date: Aug 01, 2017

Retaining Wall Repair

\$9,900.00

Semmer Landscape will repair the retaining wall the has deteriorated over the years.

Semmer will remove the existing wall to check conditions and redo the gravel base while doing that we will excavate a foot in from the sidewalk in and install a drainage pipe next to the wall so the water doesn't stay there and has a place to go we will also install 4 drainage outlets throughout the wall so the water has access to get out and not cause the wall to tilt or fall within time. Geo Textile Fabric will be installed as well to help with drainage. Once the wall is rebuilt we will power wash it all to get all the mold out and make it look like new again.

We will try to use all existing material but in case we need new material there will be an additional cost to this proposal.

15	Each	Grade 8 Limestone - Ton	
4	Each	Paver Adhesive - tube	
4	4"	Tee - 4" Drintile - 4"	
4	4"	Grate Cap - 4" Drintile - 4"	
250		Geo Textile Fabric - sq ft,	
1	5 Oz	Filter Fabric - 3x250	
10	Each	Debris	
1		4" Drintile	100 ft.

Subtotal \$9,900.00

Taxes \$0.00

Estimate Total **\$9,900.00**

Estimate authorized by: _____

Company Representative

Signature Date: _____

Estimate approved by: _____

Customer Representative

Signature Date: _____