



To: Village of Orland Park Address: 14700 Ravinia Avenue Orland Park, Illinois 60462	Contact: Gary Couch Phone: 708-403-6150 Email: gcouch@orlandpark.org
Project Name: Orland Golf View Pond Restoration & Stabilization Location: Orland Park, Illinois	Ref #: B17-073 Date: 6/12/2019 Estimator: Tom Foster

V3 Construction Group, Ltd. proposes to execute the following work:

STABILIZATION & NATIVE RESTORATION PROPOSAL

1.00 ORLAND GOLF VIEW SLOPE RESTORATION (830 LF)	\$	157,213.00
BASE PROPOSAL TOTAL:		\$ 157,213.00
<i>BID ALTERNATE #1 - INSTALL STONE TOE AT SOIL WRAP - 830 LF</i>	<i>\$</i>	<i>32,287.00</i>
<i>BID ALTERNATE #2 - RESET EXISTING FLARED END SECTIONS - 2 EACH</i>	<i>\$</i>	<i>4,000.00</i>
PROPOSAL TOTAL:	\$	193,500.00

Project Notes:

- 1.0 This proposal is valid for 30 days.
- 2.0 This proposal is to provide slope re-grading and installation of vegetated soil lifts for a detention basin in Orland Park.
- 3.0 We have not provided as-built drawings. It is our understanding that the work detailed below is considered maintenance and will not require any permitting. Permit drawings / fees are not provided in this estimate.
- 4.0 This proposal specifically excludes: bonds, permits, special insurance (waiver of subrogation, pollution liability insurance), and testing including QC/QA, handling or disposal of hazardous materials or non-hazardous special waste material, & compaction or material testing.
- 5.0 This is a "balance site" proposal. No monies are included for the removal or import of soil material. It is our understanding that sufficient topsoil is present in the slopes to provide for soil wrap installation & backfill.
- 6.0 It is V3's assessment that the Work to be performed pursuant to this Contract is neither the construction nor demolition of public works and therefore the Illinois Prevailing Wage Act does not apply to the Work to be performed pursuant to this Contract. If the Illinois Prevailing Wage Act applies to the Work, V3 reserves the right to adjust pricing.
- 7.0 This is a lump sum proposal for the scope indicated. Unit rates and quantities are provided to illustrate intended project scope and provided a basis for negotiating change orders in the event that scope is added or deleted from the contract.
- 8.0 We have provided installation of a stone toe at the face of the soil wraps as an owner directed alternate. Past projects that have included the stone toe have shown to hold up to erosion and undermining of the soil wraps very well. If the budget allows we highly recommend installation of the stone toe to ensure the longevity of the stabilization system.

Payment & Contract Notes:


- 1.0 Unless otherwise specified, the quantities for the items listed above are estimated only. Payment will be based on the final quantities installed and the applicable unit prices.
- 2.0 Net payment is due upon receipt of invoice.
- 3.0 Invoices unpaid after thirty (30) days will incur a finance charge of three percent (3.0%) per month.
- 4.0 Final payment, including any retained monies, is due immediately upon satisfactory completion of the work and receipt by purchaser of the final invoice.
- 5.0 This contract is limited to the work identified. Any additional work will be agreed to by change order and made a part of this agreement.
- 6.0 This contract shall be interpreted under the laws of the State of Illinois.

ACCEPTED: <i>The above prices, specifications and conditions are satisfactory and hereby accepted.</i>	CONFIRMED: <i>The above prices, specifications and conditions are satisfactory and hereby confirmed.</i>
Purchaser: <u>Village of Orland Park</u>	Seller: <u>V3 Construction Group, Ltd.</u>
Signature _____	Signature: _____
Printed Name: _____	Printed Name: _____
Date: _____	Date: _____



To:	Village of Orland Park	Contact:	Gary Couch
Address:	14700 Ravinia Avenue	Phone:	708-403-6150
	Orland Park, Illinois 60462	Email:	gcouch@orlandpark.org
Project Name:	Orland Golf View Pond Restoration & Stabilization	Ref #:	B17-073
Location:	Orland Park, Illinois	Date:	6/12/2019
		Estimator:	Tom Foster

1.00	ORLAND GOLF VIEW SLOPE RESTORATION (830 LF)	QUANTITY	UNIT	UNIT PRICE	TOTAL
1.10	GENERAL CONDITIONS				
1.11	Mobilization	1.000	LSUM	\$ 7,020.50	\$ 7,020.50
1.12	Community Education Meeting	1.000	EACH	\$ 350.00	\$ 350.00
1.13	Informational Pamphlet (Printing & Distribution)	1.000	LSUM	\$ 130.00	\$ 130.00
1.14	Construction Access (Mats)	370.000	SY	\$ 25.00	\$ 9,250.00
1.20	DEMOLITION				
1.21	Hand Clearing & Vegetation Removal	1.000	LSUM	\$ 4,125.00	\$ 4,125.00
1.22	Boom Spray - Non Residual / Non-Selective	1.000	LSUM	\$ 325.00	\$ 325.00
1.30	STABILIZATION				
1.31	Purchase Turbidity Curtain	250.000	LF	\$ 15.25	\$ 3,812.50
1.32	Install Turbidity Curtain	830.000	LF	\$ 2.25	\$ 1,867.50
1.33	Install Double Soil Wrap	830.000	LF	\$ 93.55	\$ 77,646.50
1.40	RESTORATION				
1.41	Seedbed Preparation	0.750	ACRE	\$ 2,300.00	\$ 1,725.00
1.42	Native Seeding	0.500	ACRE	\$ 5,000.00	\$ 2,500.00
1.43	Turf Seeding	0.250	ACRE	\$ 2,600.00	\$ 650.00
1.44	Erosion Control Blanket Installation	3,630.000	SY	\$ 2.50	\$ 9,075.00
1.45	Plug Installation (GT 38)	4,150.000	EACH	\$ 4.50	\$ 18,675.00
1.46	Herbivory Protection Fence (Goose Grid)	830.000	LF	\$ 3.20	\$ 2,656.00
1.47	Access Route (Seed & Blanket)	370.000	SY	\$ 6.50	\$ 2,405.00
1.50	NATIVE AREAS MANAGEMENT				
1.51	Weed Control (3 Years)	3.000	YEAR	\$ 4,000.00	\$ 12,000.00
1.52	Site Monitoring	3.000	YEAR	\$ 1,000.00	\$ 3,000.00
SUBTOTAL					\$ 157,213.00



V3 Construction Group, Ltd.
7325 James Avenue
Winnipeg, MB R2H 1A7
630.724.9200 phone
630.724.9202 fax
www.v3ca.com

ORLAND GOLF VIEW POND

Notes:

06/27/2017

TAF