Phone (708) 389-8119
Fax (708) 389-0837
williamquinnandsons.com

WILLIAM QUINN & SONS

LANDSCAPE CONTRACTORS

Family Owned Since 1951

3860 West 127th Street • Alsip, Illinois 60803

Proposal

PROPOSAL SUBMITTED TO	PHONE	DATE
Village of Orland Park	708-403-6100	10/8/2024
STREET	CITY, STATE AND ZIP CODE	
14700 S. Ravinia	Orland Park, IL 60462	

Centennial Park West Irrigation Addition

Directional Bore (2) areas for 2" PVC Pipe

Install concrete pad for irrigation controller

Install the following irrigation components:

(48) Hunter PGP-ADJ #3	(600) ft. 1.5" Poly Pipe
(18) PGJ-04 #2.5	(1300) ft. 1" Poly Pipe
(8) PGV-151 Valves	(200) ft. 2" PVC Mainline
(1) ICC-PED Metal	(750) ft. 18/13 Sprinkler Wire

(1) Hunter ICC I2C-824-M Metal Controller

All fittings, nipples, clamps required

Note: Village to provide electric to control panel, not included in quote

Note: Changing of Irrigation Pump Switch to Flow Switch not included in quote

We Propose hereby to furnish material and labor — complete in accordance with above specifications, for the sum of:
Thirty Nine Thousand Five Hundred Forty Seven Dollars and Fifty Three Cents dollars ($ **$ 39,547.53**

PAYMENT TO BE MADE AS FOLLOWS _____ Deposit required — balance due upon completion of job. See reverse side of sheet for guarantee, terms and conditions of payment.

Authorized Signature Brian Hamming

I have read and agree to the terms and conditions outlined in this contract.

All material is guaranteed to be as specified. All work to be completed in a workmanlike manner according to standard practices. Any alteration or deviation from above specifications involving extra costs will be executed only upon written orders, and will become an extra charge over and above the estimate. All agreements contingent upon strikes, accidents or delays beyond our control. Owner to carry fire, tornado and other necessary insurance. Our workers are fully covered by Workmen's Compensation Insurance.

Signature _____

Date _____