



A proposal for  
**VILLAGE OF ORLAND PARK, IL**  
**NAPA IBS**  
**ORLAND PARK, IL 60462**

**Quote # SF-2026-02211 Revision # 2**

**Apr 22, 2026**

**Quotation valid until: Jul 21, 2026**

**This document outlines a comprehensive truck package, comprising the following equipment. The listed equipment is designed to be installed and operated as an integrated system, ensuring full compatibility and optimal performance.**

**Front Plow**

**Plow Hitch**

**V-Box Sand and Salt Spreader**

**Prewet System**

**Chassis**

**Installation**

**NPPGov Contract Number: PS22170**

Quote prepared by: Daniel Montiel

## Package Model - PACKAGE

### PLOW

|                                   |  |
|-----------------------------------|--|
| Plow Style                        | <b>Reversible RSP/OWP</b>                                    |
| Plow Profile                      | <b>Integral Shield</b>                                       |
| Plow Moldboard Modifications      | <b>RH Mailbox Cut</b>  |
| Plow Trip Type                    | <b>Torsion Trip Edge</b>                                     |
| Plow Height                       | <b>42 inch</b>   |
| Plow Length                       | <b>11 foot</b>   |
| Plow Moldboard Material Type      | <b>Orange Polyurethane</b>                                   |
| Plow Moldboard Material Thickness | <b>3/8 inch Poly</b>   |
| Plow Moldboard Paint              | <b>Plow Frame Black, Poly Moldboard</b>                      |
| Plow Cutting Edge type            | <b>Standard</b>  |
| Plow Cutting Edge Description     | <b>Standard 5/8 X 8 Cutting Edge</b>                         |
| Plow Pushframe type               | <b>Standard Pushframe</b>                                    |
| Plow Pushframe Width              | <b>Standard Width</b>  |
| Plow Reversing Cylinders          | <b>4" x 2" Nitrided Reversing Cylinders</b>                  |
| Cushion Valve                     | <b>Cushion Valve (Standard)</b>                              |
| Cylinder Hose Kit                 | <b>Cylinder Hose Kit (Standard)</b>                          |
| Plow Running Gear Shape           | <b>No Running Gear</b>                                       |
| Plow Running Gear                 | <b>No Running Gear</b>                                       |
| Plow Hitch Type                   | <b>Quick Link Hitch</b>                                      |
| Plow Deflector                    | <b>Rubber Deflector No Logo Installed</b>                    |
| Plow Sight Marker                 | <b>36" Poly Plow Marker (Ship Loose)</b>                     |
| Parking Jack                      | <b>Parking Jack Shipped Loose</b>                            |
| Moldboard Shoes                   | <b>No Moldboard Shoe</b>                                     |
| Curb Guards                       | <b>Wrap Around Curb Guard, Pair</b>                          |
| Moldboard Bottom Angle Gussets    | <b>Standard Gussets</b>                                      |
| Blade Saver                       | <b>No Blade Saver</b>  |
| <b>Special Request</b>            |  |
| Standard 5/8 X 8 Cutting Edge     | LINE ITEM ADDITIONAL SHIPPED LOOSE CUTTING EDGE<br>(1) 81936 |

### HITCH

|                         |                                |
|-------------------------|--------------------------------|
| Truck Side Hitch Type   | <b>Low Profile</b>             |
| Hitch Family            | <b>Basic Hitch</b>             |
| Lift Cylinder           | <b>4"x2" Nitrided Cylinder</b> |
| Hitch Connection Type   | <b>Quick Link Hitch</b>        |
| Hitch Mounting Hardware | <b>No Mounting Hardware</b>    |

### FSH

|                |                                    |
|----------------|------------------------------------|
| Model          | <b>FSH - Dual Auger</b>            |
| Steel Type     | <b>201 Stainless Steel</b>         |
| Hopper Height  | <b>50" Hopper Height</b>           |
| Hopper Length  | <b>10' Hopper Length</b>           |
| Body Design    | <b>84" Wide Standard Body</b>      |
| Auger Feedgate | <b>No Rear Feedgate (Standard)</b> |

Lift Loops  
 Conveyor Type  
 Idler Grease Lines  
 Conveyor Motor  
 Hydraulic Flow Divider  
 Motor Guard  
 Spinner Disc  
 Spinner Chute  
 Spinner Extension  
 Tip Up Chute  
 Hardware Type  
 Paint  
 Primer  
 Inverted Vee  
 Top Grate Screens

Hold Down Kit  
 A-Frame  
 Chassis Frame Mount Kit  
 Trunnion/Bumper  
 Mudflap Kit  
 Body Guides  
 Leg Stand  
 Spill Shield  
 Rubber Side Shields  
 Cabshield  
 Lighting  
 Ladder  
 Side Tubes & Rear Hose Kit

Hose Kit  
 Prewet Install

**Special Request**  
 84" Wide Standard Body

**Standard Lift Loops**  
**Standard Auger Flighting**  
**Idler Grease Lines Extended to Rear**  
**Dual Auger Motors w/ Sensor**  
**Basic Hydraulic Flow Divider**  
**Auger Motor Guard (installed)**  
**20" Poly Urethane Spinner Disc**  
**Telescopic Chute w/ Dump Over (w)**  
**10" Spinner Extension**  
**No Tip Up Chute**  
**Stainless Steel Hardware**  
**Paint NA**  
**No Primer (Natural Finish)**  
**Inverted Vee Optional (Factory Installed)**  
**STD Duty Screens, Stainless Steel (Factory Installed)**  
**No Hold Down Kit**  
**No A-Frame**  
**Frame Mount Kit (No Catwalks)**  
**No Trunnion Latch**  
**No Mudflap Kit**  
**No Body Guide Kit**  
**No Leg Stand**  
**No Spill Shield(s)**  
**No Rubber Side Spill Shields**  
**No Cabshield**  
**Light Bar, 9 Light LED (Factory Installed)**  
**No Ladder**  
**SS Hyd Side Tubes, Rear Hoses (No PWS Hoses)**  
**No Hose Kit**  
**No Prewet System**

- LINE ITEM CABSHIELD TO BE PART# 179705.201 CABSHIELD, 22" X 78", 10GA (4) REAR (ILDOT) LIGHT HOLES. - SHIPPED LOOSE FOR USC INSTALL.
- LINE ITEM SUBFRAME 195579

**PWS**

Control Console Type  
 Prewet Type  
 Material Type/Support Frame  
 Tank 2 Size/Selection  
 Application  
 Tank 1 Size/Selection  
 Slurry Tube

**No Control Console**  
**Hydraulic Prewet**  
**304SS Support Frame**  
**Extra 200 Gallon Wrap-Around Tank**  
**V-box Spreader**  
**200 Gallon Wrap-Around 10' Fsh Minimum**  
**No Slurry**

Install Prewet System  
Flush Kit  
Tank Float Switch  
Air Bleed Kit  
Install Prewet with Catwalks  
Spray Nozzle Type  
Hardware Type  
Spreader Spinner Chute  
Prewet Function  
Fittings

**Special Request**

Vbox Spreader

**Prewet Installed**  
**Flush kit**  
**No Float Switch**  
**No Air Bleed Kit**  
**Install With No Catwalks**  
**Variable Displacement Hose Nozzle**  
**Stainless Steel Hardware**  
**Spreader Spinner Chute, Tele with Dumpover**  
**Hydraulic with Flow Meter No Valve (8gpm)**  
**2" Fill with 1.5" Poly Fittings**

LINE ITEM (1) 140734.304 SINGLE LANE BOOM PACK

**CHASSIS**

Chassis Supplier  
Order Type  
Chassis Make  
Chassis Model  
Chassis Model Year  
Hood Snow Door  
Hood Type  
Grille Style  
Cab Type  
Front Frame Extensions  
Front Frame Wall Type  
Front Frame Wall Thickness  
Front Frame Rail Height  
Front Bumper  
Front Frame Width  
Front Suspension Load Rating  
Set Back/Forward Axle  
Chassis Axle Quantity  
Chassis CA/CT (Usable)  
PTO/Pump Provisions  
Pump Location  
Transmission Model  
Transmission Cooler  
Backup Alarm  
Battery Box Placement  
Momentary Dash Switch Qty  
Rocker Switch Qty  
Plow Light Prep  
Beacon/Strobe Prep  
Trailer Plug  
Body builder plug  
Chassis Supplied Camera  
Tow Hooks

**Customer Supplied Chassis**  
**Turnkey Install**  
**Peterbilt**  
**548**  
**Model Year 2026**  
**No Snow Door On Hood**  
**Vocational Hood Style**  
**Stationary Grille**  
**Regular Cab**  
**20" Front Frame Extensions**  
**Single Wall Front Frame**  
**.34" Frame Rail Wall Thickness**  
**10-3/4" Frame Height**  
**OEM Front Bumper Included**  
**34" Front Frame Width**  
**Under 15K Front Suspension**  
**Axle Not Set Back/Forward**  
**Single Axle**  
**85**  
**PTO Provisions Driver Side**  
**Transmission Mount Pump**  
**Allison 3000 Transmission**  
**Standard Transmission Cooler**  
**Chassis Back Up Alarm Not Included**  
**Battery Box Under Cab**  
**No Momentary Dash Switch**  
**3 Latching Dash Switch**  
**Chassis Plow Light Ready**  
**OEM Strobe/Beacon\_switch\_wiring**  
**7 Pin Round Plug OEM Installed**  
**Bodybuilder Plug Installed**  
**No Chassis Supplied Camera**  
**Chassis Supplied Front Tow Hook**

Winch Mount  
Glad Hands  
Air Line Provision for Glad Hands  
Air Tank Placement  
Fuel Tank Location  
Fuel Tank Shape  
Def Tank Location  
Fuel Tank Size  
Passenger Seat Style

**No Chassis Winch Mount  
Glad Hands Included  
Air Line Provisions Included  
Under Frame Air Tank  
Under Driver Door Fuel Tank  
D-Shaped Fuel Tank  
Def Directly In Front Of Fuel Tank  
60-69 Gallon Fuel Tank Size  
Air Ride Passenger Seat**

## **INSTALLATION**

Chassis Delivery To Henderson  
USC Build Facility  
Installation Order Type  
Completed Truck Delivery  
Non-Henderson Equipment  
USC Paint Location  
Hooklift  
Liquid Type  
Spreader Type  
Dump Body Type  
Scraper Type  
Wing Type  
Front Plow Type  
Hitch Type  
Plow Portion Hitch  
Hitch Mount Style  
Front Bumper  
Front Tow Hooks  
Plow Markers  
Plow Rubber Deflector  
Plow Jack Install  
QD Mount Location Field

**Truck Dealer/Customer Delivers  
USC-IL  
Turnkey Install  
Henderson Delivers (100 Miles or Less)  
No Non-Henderson Equipment  
Not Required For Job  
No Job Specific Hooklift  
V-Box Prewet System  
FSH Spreader  
No Dump Body  
No Underbody Scraper  
No Wing Plow  
Reversible Plow  
Low Profile  
Plow Attachment Quick Link  
Cheek Plate Hitch Mount Kit  
OEM Bumper Cut And Split  
Tow Hooks, 44K Lb, Pair, USC Supplied  
Factory Supplied and Installed at USC  
Rubber Deflector Installed at Manufacturing  
Plow Jack Installed at Upfit  
Stainless Steel Quick Disconnect Mount, Front  
Of Bolster  
Hydraulic Drive Spreader  
Chassis Mount Spreader (V-Block)  
Not Required  
Not Required On Job  
Supplied by factory, installed at USC  
Not Required  
Not Required  
Standard Spinner Install  
Hydraulic Drive, Henderson Upfit Installed  
Supplied By Henderson Upfit, Included With  
Hydraulic Package  
Supplied By Factory  
Supplied By Factory Henderson Upfit Installed**

Spreader Drive Type  
Spreader Mount Type  
Spreader Cabshield  
Spreader Underbody Pan  
Spreader Chassis Mount Kit  
Spreader Ladder  
Spreader Bumper  
Spreader Spinner Install Type  
Liquid Drive Configuration  
Liquid Controls

Feedback Sensor  
Flush Kit

Liquid Selector Valve Required

Slurry Tube

Prewet Discharge Location

Pintle Plate information

Pintle Hook Selection

Rear Mudflap Mounting

Rear Mudflap Material

Rear Center Mudflap Mounting

Front Center Mudflap Mounting

Front Mudflap Mounting

Poly Fenders

Pintle Plate

Pintle Plate Thickness

Pintle Plate OEM Lights

Pintle Plate ICC Lights

Pintle Hook Hole Pattern

Reflective Tape

Lube System

Miscellaneous D-Ring Quantity

Exhaust Elbows

Automatic Tire Chains

Pusher Axle

Toolbox

Trailer Plug 2

Trailer Plug 1

Gladhands

Pintle Plate D-Rings

Chipper Bar

Rear Tow Hook

PDP Mount Location

Misc Electrical Supplies

GPS System

Pavement Temp Sensor

USC Light Package

Grille Light(s)

Camera Wash Kit

Camera 2 Location

Camera 1 Location

Camera Type/Monitor

Camera Quantity

Camera System

Wiper(s)

Switchbox

**Supplied By Factory, Installed At Henderson  
Upfit**

**Not Required**

**Front Or Rear**

**No OEM Light Holes, ICC/ 3/4" Combo, 10/20 ton  
combo holes, Subframe**

**20 Ton**

**Frame Mount Stainless Steel**

**Rubber Rear Mudflap No Logo**

**Not Required On Job**

**Front Center Mudflap Not Required**

**Front Mudflap Not Required**

**Poly Fenders, Full Pair, Single Axle, Stainless  
Steel Mount**

**Pre-Fab Pintle Plate Installed**

**3/4" Pintle Plate Thickness**

**No Pintle Plate OEM Lights**

**Qty 3, 3/4" ICC Lights**

**20 Ton**

**No Logo Reflective Tape 60' Linear**

**No Lube System Required**

**Not Required**

**Exhaust Elbow Not Required**

**Tire Chains Not Required**

**Pusher Axle Not Required**

**Not Required**

**Not Required For Job**

**7 Pin Trailer Plug, Truck, 7-Way RV**

**Glad Hands Fixed Straight S&E Dust Drop Pair**

**Qty 2, 1" D-Rings, 50 Degree Bend**

**Chipper Bar Not Required**

**44K Lb Pair Installed Rear**

**PDP Mounted On Back Wall**

**Misc Electrical Supplies Required**

**GPS System Not Required**

**Roadwatch, Stand Alone Display**

**72" Whelen Kit 2 Light ILDOT Standard**

**Grille Lights Not Required**

**Camera Wash Kit Not Required**

**Rear Spinner**

**Cabshield Mounted**

**Camera Type Not Required**

**2 Hydraulic Supplied Cameras**

**Camera System Included In Hydraulic Package**

**Wiper Not Required**

**No Switch Box Necessary**

License Plate Lights

Brake Controller  
Body Up Switch/Light  
Back Up Alarm Bracket  
Back Up Alarm  
Roof Beacon Light  
Worklight 2 Location  
Worklight 2 Type  
Worklight 1 Location  
Worklight 1 Type  
Worklight Quantity  
Roof Spotlight  
Mirrors  
Driving Lights  
Plow Lights Brackets

Plow Lights  
Hydraulic System Source  
Hydraulic System Manufacturer  
Control Mount Location  
Hydraulic Control Type  
PTO Type  
Reservoir Type  
Hydraulic Package  
Total Number of Quick Coupler Pairs  
Required  
Quick Coupler Upgrade  
Return Filter  
Low Oil Indicator  
High Temperature Oil Shutdown  
Low Oil Shutdown  
Valve Enclosure Mount Location  
Valve Enclosure Size  
Valve Enclosure Supplier  
Plow Pressure Relief Valve  
Stainless Steel Tubing  
Undercoat  
Touch Up Paint

**Special Request**

Fsh Spreader

**Special Request**

Spreader Cabshield Not Required

**Special Request**

Henderson Upfit Supplied License Plate Light  
Grey Housing  
Voyager Brake Controller  
Proximity Switch/Bracket/Harness  
Back Up Alarm Bracket Not Required  
97 Decibel  
Not Required  
Rear Spinner  
LED Worklight, 5" Round, Optilux  
Rear Spinner  
LED Worklight, 5" Round, Optilux  
Quantity 2 Worklights  
Not Required  
Not Required  
Driving Lights Not Required  
Stainless Steel, Freightliner, Western Star/Other,  
Pair  
ABL, Heated  
Henderson Supplied Hydraulic System  
Certified  
Floor Plate/Pedestal Mount Control  
Electric Controls  
Included In Hydraulics  
Supplied With Equipment  
Full Hydraulic Package  
2 Pair QD Couplers

Stainless Steel QD Couplers  
Supplied With Hydraulic Package  
Supplied With Hydraulic Package  
High Temp Oil Shutdown Not Required  
Not Required  
Driver Side Valve enclosure, Frame Mount  
Supplied With Hydraulic Package  
Valve Enclosure Supplied w/ Hydraulics  
No Plow Pressure Relief Valve  
SS Lines to Front and Rear of Truck  
No Undercoat Required  
No Additional Touch Up Paint

INSTALL FACTORY SUPPLIED SINGLE LANE SPRAY BOOM  
TO PREWET KIT.

INSTALL FACTORY SUPPLIED DUMP STYLE CABSHIELD  
179705.201 TO SPREADER.

72" Whelen Kit 2 Lite Ildot Standard (1)188611 LIGHT,ALLEY,PAIR,WHELEN  
**Special Request**  
Full Hydraulic Package

- ADD:
- (1)177210 FILTER,T-PORTED,HIGH PRESSURE
  - (1)160343 VALVE, PRESSURE PROTECTION

**Special Request**  
Hydraulic System Manufacturer: Certified Quote 11027221  
Certified

**Original Package Price:** \$158,080.00

**Total Package with applicable NPPGov Discount:** \$134,407.00

**Freight:** \$585.00

**Package (s):** 2

**Total:** \$264,607.72

Due to the volatility in material costs and chassis delays, pricing is subject to change at time of manufacturing and/or upfit.

Henderson offers a deposit program with additional discounts. Please contact your Henderson sales representative for more details.

All terms and conditions apply. Terms of Sale Document available at [http://www.hendersonproducts.com/assets/Terms\\_of\\_sale.pdf](http://www.hendersonproducts.com/assets/Terms_of_sale.pdf)

**Signed:** \_\_\_\_\_ **Date:** \_\_\_\_\_

**Quote notes:**