

Multi-Family Wall Separation Study 2010

This study is to determine what type of separation is required by various Municipalities

Municipality	Code	Penetrations Allowed	Separation w/ Sprinklers	Construction Type
Village of Orland Park	2006	None in center wall	1 Hour	3 Wall System
Village of Alsip	2006	Yes	1 hour	1 Wall System
Village of Bartlett	2006	None	2 Hour	1 Wall System
Village of Glenview	2006	None	2 Hour	2 Wall System
Village of Hoffman Estates	2006	None in center wall	1 Hour	3 Wall System
Village of Oak Lawn	2003	Yes if fire stopped	1 Hour	1 Wall System
Village of Palos Heights	2006	None	1 Hour	1 Wall System
Village of Schaumburg	2009	Any	1 Hour	1 Wall System
Village of Tinley Park	2006	Any	2 Hour	Concrete
City of Darien	2006	Any	1 Hour	1 Wall System
Village of Frankfort	2006	Any	2 Hour	Concrete
Village of Lisle	2003	Any	2 Hour	1 Wall System
City of Naperville	2006	Any	1 Hour	1 Wall System
City of Manhattan	2006	Any	2 Hour	1 Wall System
City of Aurora	2006	Any	1 Hour	1 Wall System
Village of Gurnee	2003	Any	1 Hour	1 Wall System
Village of Matteson	2003	None	2 Hour	2 Wall system
Village of New Lenox	2006	Any	2 Hour	1 Wall System
Village of Elmhurst	2006	Any	2 Hour - Type IA	Concrete
Village of Batavia	2006	Any	2 Hour	Concrete
City of Prospect Heights	2003	Any	2 Hour	Concrete
City of Plainfield	2006	None	2 Hour	2 wall system