


Village of Orland Park

2024 Winter RIP Tree Maintenance Project - Proposal Sheet

TREE LOCATIONS ARE HIGHLIGHTED ON THE ATTACHED MAPS All tree removals must be stump ground approximately 6-8" below grade level. All stump grindings must be hauled away to level grade. Contractors are responsible for all utility locates.

Contact Village Forester Georgie Szymczak with any questions:
312-502-8655



TREE TRIMMING - WINTER 2024

SUBDIVISION	PROPOSAL PRICE	NUMBER OF TREES TO BE TRIMMED
Brook Hills II (Tree Trimming)	\$ 4,935.00	47
Catalina West (Tree Trimming)	\$ 22,915.00	181
Kingswood and Green Valley (Tree Trimming)	\$ 6,345.00	81
Oak Meadows (Tree Trimming)	\$ 4,230.00	32
Sedgewick (Tree Trimming)	\$ 4,585.00	45
Steamstown-Meadowview (Tree Trimming)	\$ 1,410.00	18
Wedgewood Commons (Tree Trimming)	\$ 2,470.00	31
Orland Hills East (Tree Trimming)	\$ 3,175.00	22
Orland Hills West (Tree Trimming)	\$ 3,175.00	30
TOTAL TREE TRIMMING PRICE	\$ 53,240.00	487 Total

TREE REMOVALS - WINTER 2024

SUBDIVISION	PROPOSAL PRICE	NUMBER OF TREES TO BE REMOVED
Brook Hills II (Tree Removal)	\$ 4,585.00	13
Catalina West (Tree Removal)	\$ 3,525.00	4
Kingswood and Green Valley (Tree Removal)	\$ 200.00	1
Oak Meadows (Tree Removal)	\$ 1,400.00	3
Sedgewick (Tree Removal)	\$ 1,060.00	2
Steamstown-Meadowview (Tree Removal)	\$ -	0
Wedgewood Commons (Tree Removal)	\$ 645.00	1
Orland Hills East (Tree Removal)	\$ 1,060.00	2
Orland Hills West (Tree Removal)	\$ 1,400.00	2
TOTAL TREE TRIMMING PRICE	\$ 13,875.00	28 TOTAL

AUTHORIZATION & SIGNATURE

Company Name: _____ The Davey Tree Expert Co. _____

Name of Authorized Signee: _____ Bill Mareno _____

Signature of Authorized Signee: _____ *Bill Mareno* _____

Title: _____ Regional Business Developer _____ Date: _____ 11/21/2024 _____

Migratory Bird Treaty Act, the trees are to be "limbed" out to ensure public safety and the Operations Manager notified. Forestry staff will coordinate any public relations. The remaining stem or trunk shall be removed later once wildlife has vacated the tree.

D. STUMP REMOVAL AND RESTORATION WORK

1. Stump Removal

The Contractor shall remove all tree stumps and buttress roots designated by the Operations Manager or Forestry representative to a point approximately eight inches (8") below the adjacent ground level. Additionally, the Contractor shall remove all surface and sufficient subsurface roots as may be necessary to eliminate "humps" in the lawn area adjacent to the stump.

2. Site Appearance and Disposal of Stump Grindings

After the grinding (removal) of a tree stump and all associated roots has been completed, Contractor shall remove **all stump grindings and associated debris** from the site with the appropriate tools for the job within 24 Hours. Grindings, and debris shall be placed away from the curb and gutter, street, sidewalk, and private property immediately to eliminate hazards to the motoring public and pedestrians and to eliminate damage to private property. The Contractor shall also remove and dispose of any flags left by utility companies responding to J.U.L.I.E. locate requests. Disposal of Grinding debris generated by work described in this contract shall be the responsibility of the Contractor.

AUTHORIZATION & SIGNATURE

I have reviewed this documents and agree to fully comply with all specifications herein.

Company Name: THE DAVEY TREE EXPERT CO.

Name of Authorized Signee: BILL MARENO

Signature of Authorized Signee: BILL MARENO

Title: REGIONAL BUSINESS DEVELOPER Date: 11-21-24