**VICINTY MAP** 

Lot 40

10,200 sf

0.23 ac

N01'47'34"W

UNRECORDED 30' WIDE INGRESS-EGRESS

17,139 sf

0.39 ac

21,412 sf

0.49 ac

340.00' S01'47'34"E

50' P.U. & D.E.

17,147 sf

0.39 ac

EXCEPTION - UNSUBDIVIDED LANDS

493.62'

17,154 sf

0.39 ac

### FINAL SUBDIVISION PLAT GREYSTONE RIDGE

BEING A SUBDIVISION IN PART OF THE EAST HALF OF THE SOUTHWEST QUARTER OF SECTION 6. TOWNSHIP 36 NORTH, RANGE 12 EAST OF THE THIRD PRINCIPAL MERIDIAN, IN COOK COUNTY, ILLINOIS,

828.73

0.27 ac

10,935 sf

0.25 ac

10,935 sf

0.25 ac

10,935 sf

0.25 ac

\_\_N1\*43\*21\*W \_\_\_128.65\*\_

Lot 14

10,163 sf

0.23 ac

10,192 sf

0.23 ac

11,000 sf

0.25 ac

Lot 37

10,196 sf

0.23 ac

Lot 9

11,958 sf

0.27 ac

"N01'43'21"W" "128.65"

Lot 10

10,935 sf

0.25 ac

10,935 sf

0.25 ac

Lot 12

10,935 sf

0.25 ac

Lot 13

11,000 sf

0.25 ac

Lot 39

11,207 sf

0.26 ac



27-202-020-0000



Cook County Recorder of Deeds Date: 12/22/2015 03:58 PM Pg: 0

1 inch = 60 ft.

BASIS OF BEARING

ASSUMED THE SOUTH LINE, NE. 1/4 SECTION 6-36-12 TO BE S. 88' 18' 29" W.


COMMON ADDRESS

11434 139th St Orland Park, Illinois

SITE DATA GROSS AREA:

±760,408.71 SQUARE FEET OR 17.4565 ACRES

RIGHT OF WAY DEDICATION: 153,495.6115 SQUARE FEET OR 3.52 ACRES



### R-3 ZONING CRITERIA

-10,000 S.F. MINIMUM LOT SIZE -80' MINIMUM LOT WIDTH -35% BUILDING AND PAVEMENT COVERAGE (MAX.) -2.5 STORIES, 30' HEIGHT (MAX.)

· **-** - - -----N1° 43′ 21″W 1065.15′ 80.00′ 7.5′ | 7.5′ Lot 30 Lot 32 Lot 31 12,439 sf 10,231 sf 10,227 sf 10,223 sf 10,219 sf 10,215 sf 0.29 ac 0.23 ac 0.23 ac 0.23 ac 0.23 ac 0.23 ac N01'45'26"W العائدية الإ GENERAL NOTES 1. ALL AREAS ARE PLUS OR MINUS. 2. ALL EASEMENTS ARE HEREBY GRANTED. 3 ALL DISTANCE ARE IN FEET AND DECIMAL PARTS THEREOF. 4 THERE SHALL BE NO DIRECT ACCESS TO 139TH STREET FROM LOTS 26 & 27. Salaria. · 440 \* : THE CURRENT OR SUBSEQUENT TITLE HOLDERS OF LOT 40 AND OUTLOTS 41 -AND-42-SHALL BE RESPONSIBLE FOR THE MAINTENANCE THEREOF. C THE STREET ST

9930 W. 190th Street, Suite L

Mokena. Illinois 60448

708-326-4961 voice

708-326-4962 fax

**LEGEND** FOUND IRON PIPE FOUND IRON ROD O SIP SET 5/8" x 24" IRON PIPE SET MAG. NAIL CONCRETE MONUMENT BOUNDARY LINE RIGHT-OF-WAY LINE

---- PROPOSED EASEMENT LINE

1,321.73

10,200 sf

0.23 ac

**ABBREVIATIONS** FD. n north S SOUTH (###.##') RECORD DIMENSION MEASURED DIMENSION EAST W WEST FOUND IRON PIPE FOUND IRON ROD OR PIN PUBLIC UTILITY EASEMENT DRAINAGE EASEMENT BUILDING SETBACK LINE LANDSCAPE EASEMENT SQUARE FEET ARC DIMENSION

RADIUS DIMENSION

TETON DEVELOPMENT, LLC 7512 COUNTY LINE ROAD **BURR RIDGE, ILLINOIS 60527** 

PREPARED FOR:

630.920.9430

UNSUBDIVIDED LANDS

- W. LINE, E. 1/2, SW. 1/4, NE. 1/4, SEC. 6-36-12

Outlot 41 Detention Basin

113,951 sf

2.62 ac

STORMWATER MANAGEMENT

P.U. & D.E. HEREBY GRANTED

Lot 20

10,800 sf

0.25 ac

60' RIGHT OF WAY HEREBY DEDICATED TO THE VILLAGE OF ORLAND PARK

10,212 sf

0.23 ac

Lot 21

10,800 sf

0.25 ac

10,800 sf

0.25 ac

Outlot 42

Park Site

22,641 sf

0.52 ac

Lot 35

10,204 sf

0.23 ac

DRIVE

Lot 34

10,208 sf

-E. LINE, E. 1/2, SW. 1/4, NE. 1/4, SEC. 6-36-12

0.23 ac

UNSUBDIVIDED LANDS

N01'45'28"W

NO. DATE DESCRIPTION 06/30/2015 PER VILLAGE COMMENTS (06-29-2015) 6. 10/20/2015 2. 07/07/2015 EASEMENTS 07/24/2015 08/07/2015 NO CHANGES THIS SHEET

EXISTING EASEMENT LINE

DESIGNTEK SURVEYING, LLC PROFESSIONAL LAND SURVEYORS & CONSULTANTS IL Prof. Lic. No.: 184 -- 004929 License renews: April 30, 2017

FINAL SUBDIVISION PLAT DESCRIPTION SHEET NO. UTILITY EASEMENTS 1 of 2 **GREYSTONE RIDGE** DRAFTING COMPLETED: 05/06/2015 VILLAGE COMMENTS DRAWN BY: SJL PROJECT MANAGER: SJL 08/31/2015 Project No: 08-05013 FIELD WORK COMPLETED: 07/09/2014 CHECKED BY: SCALE: 1" = 60'

Lot 8

12,192 sf

0,28 ac

Lot 7

12,178 sf

0.26 ac

147.46 N01'45'26"W

12,164 sf

0.28 ac

12,150 sf

0.28 ac

12,136 sf

0.28 ac

Lot 3

12,122 sf 0.28 ac

146.77" N01'45'26"W \_\_\_\_\_\_

Lot 2

12,107 sf

0.28 ac

146.60' N01'45'26"W

Lot 1 12,093 sf 0.28 ac

\_\_\_\_\_

## GREYSTONE RIDGE

BEING A SUBDIVISION IN PART OF THE EAST HALF OF THE SOUTHWEST QUARTER OF SECTION 6. TOWNSHIP 36 NORTH, RANGE 12 EAST OF THE THIRD PRINCIPAL MERIDIAN, IN COOK COUNTY, ILLINOIS.

OWNER'S CERTIFICATE
STATE OF ILLINOIS )  SS  COUNTY OF )
COUNTY OF )
This is to certify that
Elementary: # <u>135</u> High School: # <u>230</u>
Dated at Manager, Illinais, this day of day of A.D., 20 &
Owner Owner
NOTARY PUBLIC CERTIFICATE
STATE OF ILLINOIS ) ) SS COUNTY OF )
I, I a notary public in and for the said county and state aforesaid, do hereby certify that I who is (are) personally known to me to be the same person(s) whose name(s) are subscribed to the foregoing instrument as such owner(s), appeared before me this day in person and acknowledged that he (she) (they) signed and delivered the said instruments as his (her) (their) own free and voluntary act for the uses and purposes therein set forth.
Given under my hand and notarial seal this day of, A.D., 20
Notary Public  "OFFICIAL SEAL"  BARBARA A PECZKOWSKI  Notary Public, State of Illinois My Commission Expires 8/26/2017
VILLAGE BOARD CERTIFICATE
STATE OF ILLINOIS ) ) SS COUNTY OF COOK )
Approved by the President and the Board of Trustees of the Village of Orland Park, Illinois on this
day of Jewel , A.D., 20 15, Willage President Village Clerk
CERTIFICATE AS TO SPECIAL ASSESSMENTS
CERTIFICATE AS TO SPECIAL ASSESSMENTS  STATE OF ILLINOIS )
) SS COUNTY OF COOK )
I, ANNWAVIC Mample, Village Treasurer of the Village of Orland Park, do hereby certify that

LANGUAGE CEMERAL, TAKES DELINQUENT SPECIAL ASSESSMENTS

there are no delinquent or unpaid current or forfeited special assessments or any deferred installments

thereof that have been apportioned against the tract of land included in the plat.

# FINAL SUBDIVISION PLAT

### SURFACE WATER STATEMENT

To the best of our knowledge and belief, the drainage of surface waters will not be changed by the construction of this subdivision or any part thereof, or, if such surface water drainage will be changed, reasonable provision has been made for collection and diversion of such surface waters into public areas, or drains which the owner has a right to use, and that such surface waters will be planned for in accordance with generally accepted engineering practices so as to reduce the likelihood of damage to the adjoining property because of the construction of this subdivision.

Muchael 9. Jone, PELic. # 062-055708
Professional Engineer Michael J. Ford

COOK COUNTY CLERK STAMP

COOK COUNTY CLERK SPECIAL ASSESSMENTS STAMP

RECORDER'S OFFICE OF COOK COUNTY STAMP

### STORMWATER MANAGEMENT EASEMENT PROVISIONS

An easement is hereby reserved and granted to the Village of Orland Park and to its successors and assigns over oil the areas morked "Stormwater Management Easement" on the plat hereon drawn for the perpetual right, privilege, and authority to construct, reconstruct, repoir, inspect, maintain and operate storm sewers and the storm water detention area, together with any and all necessary manholes, catch basins, connections, ditches, swales and other structures and appurtenances as may be deemed necessary by said association, over, upan, along, under and through said indicated easement, together with right of access across the property for necessary personnel and equipment to do any of the above work. the right is also granted to cut down, trim, ar remove any trees, shrubs, or other plants on the easement that interfere with the operation of the sewers or other facilities.

No permanent buildings shall be placed an said easement. No changes to the topagraphy ar storm water management structures within the easement area shall be made without the express written cansent of the Village engineer of the Village af Orland Park, but same may be used for purposes that do not then ar later interfere

The owner of the property shall remain responsible for maintenance of the Stormwater Management area and appurtenances. The Village of Orland Park will perfarm only emergency procedures as deemed necessary by the Village Engineer of the Village of Orland Park.

### PUBLIC UTILITY EASEMENT PROVISIONS

Easements are hereby reserved far and granted to the Village of Oriand Park, Illinois and ta those public utility companies operating under franchise from the Village of Orland Park, including, but not limited to, Comed, Ameritech, NiCor, Comoast and their respective successors and assigns, over all of the oreas marked "Public" Utilities & Drainage Eosements" or (P.U. & D.E.) on the plot for the perpetual right, privilege and authority to construct, reconstruct, repair, inspect, maintain and operate various utility transmission and distribution systems, community antenna television systems and including storm and/or sanitary sewers, together with any and all necessary manholes, catch basins, connections, appliances and other structures and appurtenances as may be deemed necessary by said village, aver, upon, along, under and through sald indicated easements, together with right of access across the property far necessary personnel and equipment to do any of the above work.

The right is also granted to cut down, trim ar remove any trees, shrubs or other plants on the easements that interfere with the operation of the sewers or other

No permanent buildings or abstructions shall be placed an said easements without prior written consent of grantees, but same may be used for gardens, shrubs, landscaping and other purposes that do not then or later interfere with the aforesaid uses ar rights, after installations of such facilities. Where an easement is used both for sewers and other utilities, the other utility installation shall be subject to the ardinances of the Village of Orland Park. Easements are hereby reserved for and granted to the Village of Orland Park and other governmental authorities having jurisdiction of the land subdivided hereby, over the entire easement area for ingress, egress and the performance of municipal and other governmental services, including water, starm and sanitary sewer service and

Submitted by:

Village of Orland Park

14700 Ravinia Avenue

Orland Park, Illinois 60462

708-403-6100

Return the original Mylar to:

Send all future tax bills to:

Village of Orland Park 14700 Ravinia Avenue Orland Park, Illinois 60462 708-403-6100

Teton Development, LLC 7512 County Line Road Burr Ridge, Illinois 60527 630-920-9430

PARCEL IDENTIFICATION **NUMBERS** 

27-26-202-020-0000

### **COMMON ADDRESS**

11434 139th St Orland Park, Illinois

### LANDSCAPE EASEMENT PROVISIONS

A permanent non-exclusive easement is hereby reserved for and granted to the owner(s) and to its/their successors and assigns, in, upon, across, under, over and through the oreas shown by dashed lines and labeled "landscape eosement" on the annexed plat for the purpose of the placement of trees, shrubs, bushes, lawns, other farms of vegetation, berms, identification signs and monuments.

No permanent buildings or structures shall be placed on said easement, however fences may be placed within said easement in accordance with a site plan approved by

There shall be no removal or destruction of trees and plants within the easement area, except to the extent that each activities are undertoken to remove dead or diseased trees or plants and/or in occordance with a landscaping maintenance plan approved by the Village of Orland Park.

Na term or condition contained in this easement relating to landscaping, entry sign or manumentation shall limit ar preclude the exercise of any rights granted pursuant to any other easement provision reserved and/or granted on the annexed plat for ony other purpose londscape easement provisions.

### NI-COR EASEMENT PROVISIONS

its successors and aesigns, in all platted "P.U. & D.E." areas all streets and other public ways and places shown on this plat; said eacement to be for the installation, maintenance, relocation, renewal, and removal of gas mains and appurtenances for the purpose of serving all areas shown on this plat, as well as other property, whether or not contiguous thereto. no buildings or other structures shall be constructed or erected in any such easement areas, streets, alleys or other public ways ar places, nar shall only other use be made thereof which will interfere with the easements reserved and granted herein.

> EASEMENT PROVISIONS An easement for serving the subdivision and other property with electric and communication service is hereby reserved far and granted to

### Cammonwealth Edison Company

and SBC — Ameritech Illinois a.k.o. Illinois Bell Telephone Company, Grantees,

their respective licensees, successors, and assigns, jointly and severally, to construct, aperate, repair, maintain, modify, reconstruct, replace, supplement, relocate and remove, from time to time, poles, guys, anchors, wires, cables, conduits, manholes, transformers, pedestals, equipment cabinets or ather facilities used in connection with overhead and underground transmission and distribution of electricity, cammunications, sounds and signals in, over, under, across, along and upon the surface of the property shown within the dashed or dotted lines (or similar designation) on the plat ond marked "Easement", "Utility Eosement", "Public Utility Easement", "P.U.E" (ar similar designation), the property designated in the Declaration of Condominium and/or on this plat as "Cammon Elements", and the property designated on the plat os "common area or areas", and the property designated on the plat far streets and alleys, whether public or private, together with the rights to install required service connections over or under the surface of each lot and common area or areas to serve improvements thereon, or an adjacent lots, and common area or areas, the right to cut, trim or remove trees, bushes, roots and saplings and to clear abstructions from the surface and subsurface as may be reasonably required incident to the rights herein given, and the right to enter upon the subdivided property for all such purposes. Obstructions shall not be placed over Grantees' facilities or in, upon or over the property within the dashed or dotted lines (or similar designation) marked "Easement", "Utility Easement", "Public Utility Easement", "P.U.E" (or similar designation) without the prior written cansent of Grantees. After installation of any such facilities, the grade of the subdivided property shall not be aftered in a manner so as ta interfere with the proper aperation and maintenance thereof.

The term "Common Elements" shall have the meaning set forth for such term in the "Condominium Property Act", Chapter 765 ILC\$ 605/2, as amended from time

The term "common area or areas" is defined as a lot, parcel or area of real property, the beneficial use and enjayment of which is reserved in whole or as an appurtenance to the separately owned lots, parcels or oreas within the planned development, even though such be otherwise designated on the plat by terms such as "outlots", "common elements", "open space", "open area", "common ground", "parking" and "common area". The term "common area ar areas", and "Comman Elements" include real property surfaced with interior driveways and walkways, but excludes real property physically occupied by a building, Service Business District or structures such as a poal, retention pand or mechanical equipment Relocation of facilities will be done by Grantees ot cast of the Grantor/Lot Owner, upon written request.

### PUBLIC UTILITY AND DRAINAGE EASEMENT PROVISIONS

Easements are hereby reserved for and granted to the Village of Orland Park, Illimois and to those public utility companies operating under franchise from the Village of Orland Park, including, but not limited to, Comed, Ameritech, NiCar, Comoast and their respective successors and assigns, over all of the areas marked "Public" Utilities & Drainage Easements" or (P.U. & D.E.) an the plot for the perpetual right, privilege and authority to construct, reconstruct, repair, inspect, maintain and aperate various utility transmission and distribution systems, community antenna television systems and including storm and/or sanitary sewers, together with any and all necessary manholes, catch basins, cannections, oppliances and other structures and appurtenances as may be deemed necessary by soid village, over, upon, along, under and through said indicated easements, together with right of access across the property for necessary personnel and equipment to do any of the above work.

The right is also granted to cut down, trim or remove any trees, shrubs or other plants on the easements that interfere with the operation of the sewers or ather

No permanent buildings or obstructions shall be placed on said easements without prior written consent of grantees, but same may be used for gardens, shrubs, landscaping and other purposes that do not then or later interfere with the aforesaid uses or rights. after installations of such facilities, the grade of said easement sholl shall not be altered in a manner as to interfere with the proper operation and maintenance thereof.

Where an easement is used both far sewers and other utilities, the ather utility installation shall be subject to the ordinances of the Village of Orland Park.

Easements are hereby reserved for and granted to the Village of Orland Park and other gavernmental authorities having jurisdiction of the land subdivided hereby, over the entire easement area for ingress, egress and the performance of municipal and other governmental services, including water, storm and sanitary sewer service and

### SURVEYOR'S CERTIFICATE

STATE OF ILLINOIS

COUNTY OF WILL

This is to certify that I, Steven J. Laub, an Illinois Professional Land Surveyar, No. 035-003160, have surveyed and subdivided the following described property:

The East Half, (Except the west 228.0 feet of the sauth 493.62 feet thereof) of the Southwest Quarter of the Northeast Quarter of Section 6, Township 36 North, Range 12 East of the Third Principal Meridian, in Cook County,

as shown by the Annexed Plat which is a correct representation of said survey and subdivision.

I further certify that this Subdivision lies within the city limits or within 1.5 miles of the corporate limits of the Village of Orland Park, Illinois, which has adopted a Municipal Plan and is exercising special powers authorized by Article 11, Division 12 of the Illinois Municipal Code, as now and hereafter amended and that all regulations enacted by the Village of Orland Park relative to plats and subdivisions have been complied with in the preparation of this

I further certify that iron pipes will be set at all lot corners except where concrete monuments are indicated upon the completion of the final grading, and that the plat hereon drawn correctly represents said survey and subdivision.

I further certify that the subject property lies within Zone "X" (areas outside the 0.2% annual chance flood plain) as defined by the Federal Emergency Management Agency's (FEMA) Flood Insurance Rate Map (FIRM) of Cook County and Unincorporated Areas, Community Panel No. 17031C0594J, map revised August 19, 2008.

I further hereby grant permission to a representative of the Village of Orland Park to record this plat. Said representative shall show proper identification and provide this surveyor with a recorded copy of said plat.

Dimensions are given in feet and decimal parts thereof and all curve lengths shown are arc dimensions.

Given under my hand and seal at Mokena, Illinois, this 20th day of October A.D., 2015

Illinois Professional Land Surveyor No. #035-00316 License expires on November, 30, 2016





Mullane F

Mage Treasurer

9930 W. 190th Street, Suite L Mokena, Illinois 60448 708-326-4961 voice 708-326-4962 fax

PREPARED FOR: TETON DEVELOPMENT, LLC 7512 COUNTY LINE ROAD **BURR RIDGE, ILLINOIS 60527** 630.920.9430

REVISIONS NO. DATE DESCRIPTION DATE DESCRIPTION NO. 1, 06/30/2015 PER VILLAGE COMMENTS (06-29-2015) 6. 10/20/2015 NO REVISIONS THIS SHEET NO REVISIONS THIS PAGE 07/07/2015 3. 07/24/2015 OWNER CHANGE LANDSCAPE PROVISIONS 4. 08/07/2015 5. 08/31/2015 VILLAGE COMMENTS

FINAL SUBDIVISION PLAT SHEET NO. 2 of 2 GREYSTONE RIDGE DRAFTING COMPLETED: 05/06/2015 PROJECT MANAGER: SJL DRAWN BY: SJL 08-05013 Project No: FIELD WORK COMPLETED: CHECKED BY: SCALE: 1" = N/A