



April 28, 2014

Frank Stec  
Village of Orland Park  
14700 S. Ravinia Way  
Orland Park, IL 60462

Dear Frank:

Thank you for the opportunity to provide this revised proposal on the A/V systems per my walk through with Norm Johnson.

We identified the following requirements;

**Boardroom:**

- Install (3) wall mounted 70" displays, (2) on swing arm wall mounts, (1) tilt wall mount
- Install scaler/switcher within dais for presenter laptop presentations via HDMI, Display Port & VGA/Audio inputs
- Distribute signal to each of the (3) 70" displays and existing audio system
- Your staff will run provided shielded CAT6 cabling, provide AC power & 3/4" surface mounted plywood for displays

**Boardroom**

**Display System**

<u>Item</u>	<u>Qty</u>	<u>Description</u>
1	3	Sharp LC-70LE650U LED TV
2	2	Chief TS525TU Swing Arm Wall Mount
3	1	Chief LTMU Tilt Wall Mount

Display System Cost \$7,114

**Computer Distribution System**

The Atlona scaler/switcher will accommodate (1) HDMI & (1) VGA/audio inputs with CAT 5 output. We'll provide 15' VGA/audio & HDMI cables for input from laptop to scaler/switcher. Output of scaler will be routed to existing equipment rack via CAT extenders. Audio will be routed to existing mixer/amplifier.

HDMI output of Cat6 receiver will be routed to the Atlona HD-CAT-4, 1x 4 distribution amplifier, to each of the (3) displays.

<u>Item</u>	<u>Qty</u>	<u>Description</u>
1	1	Atlona AT-HDVS-TX, Transmitter/Switcher
2	1	Atlona AT-HDVS-RX, Receiver/Scaler
3	1	Atlona AT-HD-CAT-4, 1x4 Distribution Amplifier/Transmitter
4	3	Atlona AT-HDRX, Receiver
5	1	Kramer VGA/Audio Micro Cables, HDMI cables & Display Port Adapter

Computer Distribution System Cost \$2,194

Total Equipment Cost \$9,308

AV TechSource Installation \$1,520  
AV TechSource Cable, Connectors & Parts \$500

**Total Boardroom System Cost** **\$11,328**



Pricing excludes applicable sales tax and freight. Terms are net 15 days. Please allow 2-3 weeks for installation upon receipt of P.O.

Thanks for the opportunity.

Sincerely,

*Scott A. Tholl*

Scott A. Tholl  
System Specialist  
AV TechSource, Inc.  
847-471-8450



Terms and Conditions

This proposal includes installation, set-up, and checkout of all equipment with the EXCEPTION of AC power, network cabling, floor box, table hole cutting and conduit. Installations of these exceptions are the responsibility of owner and/or the site electrical contractor. AV TechSource will honor all manufacturers' warranties from date of invoice. Lighting fixtures, light dimming system, high voltage wiring of light dimmers, carpeting, painting, and equipment cabinets except where specifically listed are the responsibility of the owner.

Terms on invoices are net 15 days. Labor is quoted on an "as normal" basis. Our quote does not allow for delays in construction or imposed deadlines which require overtime. Approved overtime will be billed in addition to quoted labor charges.

The prices in this recommendation report will be honored for a minimum of 30 days after which they are subject to any manufacturer's price increases. Freight charges are FOB shipping point and are additional. Applicable taxes will be added to the prices shown in the proposal.

If this proposal meets with your approval please sign as indicated below;

Date: \_\_\_\_\_

Approved By: \_\_\_\_\_

Signature: \_\_\_\_\_

P.O. #: \_\_\_\_\_