



A proposal for
VILLAGE OF ORLAND PARK, IL
NAPA IBS
ORLAND PARK, IL 60462

Quote # SF-2025-00064 Revision # 1

Jun 11, 2025

Quotation valid until: Sep 9, 2025

This document outlines a comprehensive truck package, comprising the following equipment. The listed equipment is designed to be installed and operated as an integrated system, ensuring full compatibility and optimal performance.

Mark 3 Dump Body

Chassis

Installation

NPPGov Contract Number: PS22170

Quote prepared by: Daniel Montiel

Package Model - PACKAGE

Mark 3

Headsheet Thickness	12 Gauge
Body Style	Mark 3 Telescopic Hoist
Body Length	9' Body Length
Side Material Thickness	10 Gauge
Headsheet Style	Tapered Headsheet with Light Boxes
Side Style	Quick Release Fold Down Sides
Floor Material	3/16" AR400
Body Material	201 Stainless Steel
Side Height	13" Side Height (19" Tailgate)
Headsheet Window	No Window in Headsheet
Headsheet Height	53" Clearance Headsheet W/integral Cabshield
Rear Bolster Light Holes	1 Light Hole Each Side
Front Marker Light hole	No Front Marker Light Hole
Cabshield Light Hole QTY/Location	2 Forward 1 Each Side 2 Rear Facing
Light Pack Type	Standard Light Pack
Tailgate Thickness	10 Gauge
Tailgate Type	Quick Release Tailgate With Offset
Coalchute	No Coalchute Required
Hoist type	Double Acting Telescopic Hoist
Hydraulic Pump and Reservoir	No Hyd Pack
Hoist/Subframe Installed	Telescopic Hoist/Subframe Installed
Finish/Primer	No Primer (Stainless Steel Finish)
Ship Loose Window	No Ship Loose Windows
Tailgate Chain Extension for TGS	No TGS Tailgate Chain Extension
Vibrator Bracket	No Vibrator Bracket

Special Request

53" Tapered Int Cs,No Wndw,12G

**BOXED IN WIRE,LAY BETWEEN CABSHIELD LIGHT BOXES

**REF COP/SHOP 289154/821408

Special Request

(2)Frwd,(1)Ea Side,(2)Rear Lh

(4)REAR FACING LIGHT HOLES (Ref 289154/821408)

CHASSIS

Chassis Supplier	Customer Supplied Chassis
Cab Type	Regular Cab
Chassis Make	Ford
Chassis Model	F450
Chassis Model Year	Model Year 2025
Hood Type	Standard OEM Hood Style
Grille Style	Stationary Grille
Hood Snow Door	No Snow Door On Hood
Front Frame Extensions	No Front Frame Extensions

Front Bumper
 Chassis CA/CT (Usable)
 Set Back/Forward Axle
 Chassis Axle Quantity
 Front Suspension Load Rating
 Backup Alarm
 Battery Box Placement
 Momentary Dash Switch Qty
 Rocker Switch Qty
 Plow Light Prep
 Beacon/Strobe Prep
 Trailer Plug
 Bodybuilder plug
 Tow Hooks
 Glad Hands
 Air Line Provision for Glad Hands
 Air Tank Placement
 Fuel Tank Location
 Fuel Tank Shape
 Def Tank Location
 Fuel Tank Size
 Passenger Seat Style

OEM Front Bumper Included
60
Axle Not Set Back/Forward
Single Axle
Under 15K Front Suspension
Chassis Backup Alarm Included
Battery Box Under Cab
5 Momentary Dash Switch
6 Latching Dash Switch
Chassis Plow Light Ready
No OEM Supplied Beacon/Strobe Prep
7 Pin Round Plug OEM Installed
Bodybuilder Plug Installed
Chassis Supplied Rear Tow Hook
Glad Hands Not Included
No Air Line Provisions
Air Tank Location Not Specified
Under Driver Door Fuel Tank
Rectangular Fuel Tank
Def Directly Behind Fuel Tank
50-59 Gallon Fuel Tank Size
Fixed Passenger Seat

INSTALLATION

USC Paint Location
 Chassis Delivery To Henderson
 USC Build Facility
 Installation Order Type
 Liquid Type
 Spreader Type
 Dump Body Type
 Scraper Type
 Wing Type
 Front Plow Type
 Hitch Type
 Completed Truck Delivery
 Hooklift
 Non-Henderson Equipment
 Dump Body Floor Length
 Dump Body Rear Profile
 Weld On Winches
 Def Tank Filler Tube Mod
 Fuel Filler Neck Mod, Ford/Dodge
 Body Liner
 Rubber Mounting Pads
 Tarp Brand

Not Required For Job
Truck Dealer/Customer Delivers
USC-IL
Turnkey Install
Not Required For Job
No Spreader Installed
Mark 3
No Underbody Scraper
No Wing Plow
No Front Plow
No Hitch Installed
Customer Pick-Up
No Job Specific Hooklift
No Non-Henderson Equipment
9' Floor Length
Straight Tailgate And Apron
No Winches Required
Def Fill Tube Mod Not Required
Fuel Neck Modification Installed
Not Required
No Rubber Mounting Pads Required
Tarp Not Required

Sideboards	Wood Side Boards, Supplied At Henderson
Dump Body Vibrator	Upfit, No Paint
Shovel Holder Location 1	Not Required On Job
Shovel Holder Style	Driver Side Body
	Stainless Steel Spring Loaded Shovel Holder
	With Bracket
Shovel Holder Quantity	1 Henderson Upfit Supplied Shovel Holder
Ladder(s)	Not Required
Grab Handles	Not Required
Steps	No Steps Required
Asphalt Lip	No Asphalt Lip Required
Cabshield Install	Cabshield Installed By Factory
Pressure Protection Valve	Pressure Protection Valve Not Required
Tailgate Release Type	Manual Tailgate Release
Tailgate Style	Standard Tailgate
Dump Body Material	Stainless Steel Dump Body
Dump Body Cylinder Type	Double Acting Hoist Cylinder
Dump Body Hoist Type	Telescopic Hoist With Subframe, Internal
	Doghouse
Special Request	No
Pintle Plate information	1 Ton Plate
Pintle Hook Selection	Not Required
Rear Mudflap Mounting	Swinging Stainless Steel Mount
Rear Mudflap Material	Rubber Rear Mudflap No Logo
Rear Center Mudflap Mounting	Not Required On Job
Front Center Mudflap Mounting	Not Required
Front Mudflap Mounting	Not Required
Poly Fenders	1 Ton, Poly Fenders, Stainless Steel Mount
Pintle Plate	Pre-Fab Pintle Plate Installed
Pintle Plate Thickness	5/8" Pintle Plate Thickness
Pintle Plate OEM Lights	No Pintle Plate OEM Lights
Pintle Plate ICC Lights	Qty 3, 3/4" ICC Lights
Pintle Hook Hole Pattern	10 Ton
Reflective Tape	No Logo Reflective Tape 60' Linear
Lube System	No Lube System Required
Miscellaneous D-Ring Quantity	Not Required
Exhaust Elbows	Not Required
Automatic Tire Chains	Not Required
Pusher Axle	Pusher Axle Not Required
Toolbox 1 Mount Location	Passenger Side
Toolbox 1 Mount Brackets	Stainless Mount Bracket
Toolbox 1 Material	Stainless Steel
Toolbox 1 Size	18"x18"x24"
Toolbox	One Installed
Trailer Plug 2	Not Required For Job
Trailer Plug 1	Remount OEM Trailer Plug (qty 1)

Gladhands
 Pintle Plate D-Rings
 Chipper Bar
 Rear Tow Hook
 PDP Mount Location
 Misc Electrical Supplies
 Plow Lights
 Driving Lights
 Mirrors
 Roof Spotlight
 Worklight Quantity
 Roof Beacon Light
 Roof Light Type
 Back Up Alarm
 Back Up Alarm Bracket
 Body Up Switch/Light
 Brake Controller
 License Plate Lights
 Switchbox
 Wiper(s)
 Camera System
 GPS System
 Pavement Temp Sensor
 USC Light Package
 Grille Light(s)
 Dump Body Rear Lighting
 Dump Body Light Box
 Rear Bolster Light Position 1 from
 Bottom
 Dump Body Side Bolster Lighting
 Cabshield Front Light Quantity
 Cabshield Rear Facing Light Type
 Cabshield Rear Facing Light Quantity
 Cabshield Side Facing Strobe Color
 Cabshield Side Facing Light QTY
 Cabshield Front Strobe Light Color
 Cabshield Beacon Brightness
 Cabshield Beacon Mount
 Cabshield Beacon Mounting
 Cabshield Beacon Light
 Hydraulic System Source
 Hydraulic System Manufacturer
 Hydraulic Control Type
 PTO Type
 Reservoir Type
 Hydraulic Package

Glad Hands Not Required
Qty 2, 1" D-Rings, 50 Degree Bend
Chipper Bar Not Required
Remount OEM
PDP Mounted Under Passenger Seat
Misc Electrical Supplies Required
Not Required
Not Required
Not Required
Not Required
Roof Mount
LED Beacon 360 Deg, Single Direct
97 Decibel
Back Up Alarm Bracket Installed
Trucklite Body Up Switch/Light
Supplied with Chassis
Remount OEM License Plate Light
No Switch Box Necessary
Wiper Not Required
Not Required
Not Required
Not Required
Not Required
2 Mini Flash With Bracket
1 Each Side
Not Required
Stop/Tail/Turn/Backup

3/4" Round (Red)
2 Forward Facing Light Holes
(2) Stop/Tail/Turn Lights
2 Rear Facing Light Holes
Amber 6" Strobes
Side Facing Light Pair
Amber 6" Strobes
Standard Cabshield Beacon Brightness
Top Mount
Self Leveling Cabshield Beacon Mount, SS
LED Cabshield Beacon (360 Deg), Amber
Henderson Supplied Hydraulic System
Certified
Electric Controls
Included In Hydraulics
Reservoir Supplied With Hydraulics
1 Ton Hydraulic Package

Quick Coupler Upgrade
Return Filter
Low Oil Indicator
High Temperature Oil Shutdown
Low Oil Shutdown
Valve Enclosure Mount Location
Valve Enclosure Size
Valve Enclosure Supplier
Hydraulic System Type
Body Paint Type
Clear Coat Finish
Undercoat
Touch Up Paint

Special Request

PRE FAB PINTLE PLATE
INSTALLED

Special Request

LED
BEACON,360DEG,SINGLE,DIRECT

Special Request

RR FCE CS LT:(2) STT

Special Request

CERTIFIED

Special Request

INCLUDED IN HYD

Standard QD Couplers
Supplied With Hydraulic Package
Not Required
Not Required
Not Required
Driver Side Valve enclosure, Frame Mount
Supplied With Hydraulic Package
Valve Enclosure Supplied w/ Hydraulics
Central Hydraulic Transmission Mount
Natural Finish (SS Only)
No Clear Coat Finish Required
No Undercoat Required
No Additional Touch Up Paint

Pintle Plate to be HTE356

To be mounted on Cab shield

Add 2 Amber 6" Strobe lights, PART# 160014 (four rear facing light holes).

QUOTE# 11025920

Install offset for basic 1T Hydraulic PKG ILO Full
HYD PKG Install.

Original Package Price: \$55,927.00

Total Package with applicable NPPGov Discount: \$45,860.14

Freight: \$311.00

Package (s): 1

Total: \$46,171.14

Due to the volatility in material costs and chassis delays, pricing is subject to change at time of manufacturing and/or upfit.

Henderson offers a deposit programe with additional discounts. Please contact your Henderson sales representative for more details.

All terms and conditions apply. Terms of Sale Document available at
http://www.hendersonproducts.com/assets/Terms_of_sale.pdf

Signed:_____ **Date:**_____

Quote notes: