



ORLAND PARK

#26-022

LaGrange Rd Irrigation Maintenance

PROJECT DETAILS

Scope of Work

1. Spring Start-Up
 - a. Reaffix RPZ Backflow Preventers and Water Meters
 - b. Pressurize and Run system
 - c. Set timers accordingly with in Village of Orland Park Ordinance specifications
 - d. Adjust spray patterns as needed to ensure proper coverage
 - e. Make any necessary routine repairs.

2. Fall Shut Down
 - a. Blow out all lines to remove water
 - b. Remove RPZ and Meters and Return to the Village of Orland Park

3. In-Season Irrigation System Maintenance
 - a. Systems must be run and inspected 2 times throughout the summer
 - b. Adjust run times as needed as weather conditions dictate.
 - c. Make any necessary routine system repairs.

LOCATION OF WORK AND SPECIFICATIONS:

The Proposal Specifications for this RFP #26-022 are attached as *Exhibit A*.

Exhibit A- Build Maps for the entire LaGrange Rd Systems

It is expressly understood and agreed to by both Parties that in no event shall the total amount to be paid by the Village for the complete and satisfactory performance of services, exceed the proposed amount. Said price shall be the total compensation for Contractor's performance hereunder including, but not limited to, all work, deliverables, materials, supplies, equipment, subcontractor's fees, and all reimbursable travel and miscellaneous or incidental expenses to be incurred by Contractor. In the event the Contractor incurs cost in excess of the sum authorized for service, the Contractor shall pay such excess from its own funds, and the Village shall not be required to pay any part of such excess, and the Contractor shall have no claim against the Village on account thereof. For the avoidance of doubt, in no event shall Contractor be entitled to receive more than the proposed amount and this amount includes all costs incurred by Contractor in connection with the work and services authorized hereby, including, but not limited to: (i) any known or unknown and/or unexpected condition(s); (ii) any and all unforeseen difficulties; (iii) any unanticipated rises in the cost of labor, materials or equipment, changes in market or negotiating conditions, and errors or omissions made by others; (iv) the character of the work and/or services to be performed; and (v) any overrun in the time or cost necessary for the Contractor to complete the work due to any causes, within or beyond its control. Under no circumstances shall the Village be liable for any additional charges if Contractor's actual costs and reimbursable expenses for such work, service or deliverable exceed the proposed amount. Accordingly, Contractor represents, warrants and covenants to the Village that it will not, nor will Contractor have anyone on its behalf, attempt to collect an amount in excess of the proposed amount agreed to by the Contractor.