


## Village of Orland Park

### 2025 Fall Tree Removal Project - Proposal Sheet

All tree removals must be stump ground approximately 6-8" below grade level. All stump grindings must be hauled away to level grade. Contractors are responsible for all utility locates.

Contact Village Forester Georgie Szymczak with any questions:  
312-502-8655



### TREE REMOVALS

ADDRESS	JOB SITE NUMBER	NUMBER OF TREES TO BE REMOVED / STUMPED	DBH	COMMENTS
14955 El Cameno Real Drive	#15	1	23"	Silver Maple
West of Ravinia Ave and 151st Street	#17	10	Various (Small DBH)	Crabapples Under <b>Powerlines</b> Across from Police Department on 151st St (North Side of Street)
7425 Tiffany Dr	#6	1	24"	Cottonwood
9155 Brookside Court	#5	1	20"	Pear Tree Along Pond Shoreline, West of House
15412 Primrose Court	#8	1	30"	Silver Maple
15365 Orchid Court	#7	1	29"	Silver Maple
8509 Hemlock Street	#11	1	26"	Silver Maple
8320 Sunset Ridge Court	#9	4	26,27,29,39"	All Silver Maples
8554 Fir Street	#13	1	26"	Silver Maple
8546 Fir Street	#12	1	40"	Silver Maple
9316 Birch Street	#4	1	27"	Silver Maple
14517 Woodland Avenue	#1	1	25"	Oak (far west closest to street)
8401 Golfview Drive	#10	5	20,20,21,21,21"	All Ash
8919 147th Street	#18	3	21,23,26"	All Silver Maples
14671 West Avenue	#3	1	25"	White Oak (in greenspace north of building)
14700 Park Lane	#2	1	21"	Burr Oak (in frisbee golf course)
9110 Caddy Court	#14	1	36"	Silver Maple
15249 Huntington Court	#16	4	19" (HL), 11,14,14" (RM)	Honey Locust and Red Maple near <b>Powerlines</b>
8200 Eynsford Drive	#17	6	16,18,19,19,20" (L), 21"(CA)	Linden and Crabapple
13701 92nd Avenue	#20	1	25"	Siberian Elm
10701 Churchill Drive	#21	4	7,7,24,31"	All Elms
<b>LUMP SUM TREE REMOVAL PRICE</b>	\$ 49,800.00	50		

### AUTHORIZATION & SIGNATURE

Company Name: Winkler Tree and Lawn Care

Name of Authorized Signee: Patrick Leatherman

Signature of Authorized Signee: [Signature]

Title: District Manager Date: 9-12-25

# **Village of Orland Park Tree Removal Specifications**

## **A. GENERAL REQUIREMENTS**

### **1. Advance Notice to Village by Contractor**

The Contractor shall notify via email the Operations Manager or the Consulting Municipal Arborist representative prior to beginning work each day on this contract. The Contractor shall provide weekly updates on the progress of all work. Following the completion of all work, the Contractor inform the Village that the project is complete.

### **2. Advance Notice to Residents by Contractor**

The Contractor shall post suitable advance notice signs (at least 24 hours but not more than 2 days prior to performing work in that location) on streets scheduled to be pruned. Signs are to be posted in both parkways, at intersection corners, and suitable intervals, facing all directions of travel on horses with signage provided by the Village of Orland Park. The Contractor, immediately upon completion of work on each street, shall remove all such signs. The sign used must indicate the type of work that is planned for the area (i.e. pruning), the date range it is planned for, and any other language approved/required by the Municipality. The Contractor is responsible for all advance notice to residents and this item is incidental to the cost of the overall contract work.

### **3. Timeframes and Completion Requirements**

The Contractor shall provide the Village with a proposed project schedule within (10) days of the purchase order being issued. All work shall be completed by **December 1, 2024, unless otherwise approved by the Operations Manager.**

### **4. Site Appearance and Clean-Up**

Tree removals and/or pruned limbs and branches temporarily placed in the parkway area shall be placed in such a manner as to eliminate any obstruction to motor vehicles and pedestrians including streets, driveways and sidewalks. At all times, pruning crews shall not advance more than 1 block ahead of chipping/clean-up crews.

The Contractor shall clean up the site and remove and dispose of all debris. Site cleanup shall include removal of sawdust, small twigs, chips, leaves, trunks and limbs from the street, curb, parkway, sidewalk, private lawns and driveways with the appropriate tools for the job. The site shall be returned to the same state it existed in prior to the pruning work. Under no circumstances shall any materials be allowed to lie on the parkway overnight.

As pruning may occur during or after snow events, some debris may filter down through the snow and may not be immediately accessible for clean-up. In these instances, it is the responsibility of the Contractor to re-clean and rake up debris in these areas within 2 to 3 days after the snow melts. No extra payment shall be made for this clean-up work.

### **5. Protection of Property**

The Contractor shall take all necessary precautions to eliminate damage to adjacent trees and shrubs, lawns, curbs, walks, or other real or personal property. Holes made in lawns, regardless of size, shall be filled with black dirt and seeded with a turf grass lawn seed mix. Any damage shall be rectified within ten (10) days. Equipment shall not enter upon private property unless the property owner(s) consent or the Operations Manager.

street with significant traffic during rush-hours shall be performed between the hours of 9:00 a.m. and 4:00 p.m.

#### **10. Safety Standards**

All equipment to be used and all work to be performed shall be in full compliance with the most current revision of the *ANSI Z133.1-2012 Safety Requirements for Arboricultural Operations*, or as amended. Contractor personnel exposed to public vehicular traffic shall wear warning vests or other suitable garments marked with or made of reflectorized material. At a minimum, this includes ANSI Class 2 garments.

#### **11. Traffic Control**

The Contractor shall conduct its operations in a manner that will not interrupt pedestrian or vehicle traffic except as approved by the Village. The work area shall be confined to the smallest area possible to allow maximum use of the street or sidewalk and to minimize any hazard to traffic or pedestrians. The Contractor shall provide adequate traffic control for work area protection in compliance with the Federal Highway Administration *Manual on Uniform Traffic Control Devices for Streets and Highways* (MUTCD) current edition, the State of Illinois *Illinois Vehicle Code*, the Illinois Department of Transportation *Highway Standards*, and the Illinois Department of Transportation *Handbook of Traffic Engineering Practice for Small Cities*. All personnel, signs, barricades, and any other items or devices necessary shall be provided by the Contractor. The Village shall make no separate payment for this work. Traffic control shall include but not be limited to the following:

1. All work vehicles shall be positioned on the same side of the street as the work site.
2. Whenever possible the work site on a two-lane street or highway shall be confined to one traffic lane leaving the opposite lane open to traffic.
3. Work area protection shall consider the duration of the project, the size of the project, the lanes of traffic, the volume of traffic, the speed limit, and the distance to the work area from the pavement.
4. Work vehicles shall have the flasher light lit but not as a substitute for any traffic control devices for work area protection that may be necessary.
5. Under certain field conditions such as hills and curves, the spacing of the traffic control devices shall be adjusted as necessary.
6. Warning signs such as "Men Working" shall be diamond shaped having a black symbol or message on an orange reflective background. Such signs shall have a minimum size of 36 inches by 36 inches with a maximum size of 48 inches by 48 inches. Such signs shall be posted at a minimum height of 12 inches above the pavement.
7. Cones used as daytime channeling devices shall be at least 18 inches tall, conical or tubular in shape with a broadened base, and orange in color. Cones shall be spaced equal in feet to the posted speed limit or closer along the taper length.
8. Channeling devices such as cones shall be positioned to provide adequate taper length before the work area to guide traffic through the work area. Tapers approaching the work zone shall be:

\* 150' minimum for posted speed limits 35 mph or higher

\* 50' minimum for posted speed limits 30 mph or less

Except for infectious diseased trees or structurally hazardous trees, should the Contractor discover a tree marked for removal has interesting wildlife such as owls or songbirds or any birds protected by the Migratory Bird Treaty Act, the trees are to be "limbed" out to ensure public safety and the Operations Manager notified. Forestry staff will coordinate any public relations. The remaining stem or trunk shall be removed later once wildlife has vacated the tree.

### C. STUMP REMOVAL AND RESTORATION WORK

#### 1. Stump Removal

The Contractor shall remove all tree stumps and buttress roots designated by the Operations Manager or Forestry representative to a point approximately eight inches (8") below the adjacent ground level. Additionally, the Contractor shall remove all surface and sufficient subsurface roots as may be necessary to eliminate "humps" in the lawn area adjacent to the stump.

#### 2. Site Appearance and Disposal of Stump Grindings

After the grinding (removal) of a tree stump and all associated roots has been completed, Contractor shall remove **all stump grindings and associated debris** from the site with the appropriate tools for the job within 24 Hours. Grindings, and debris shall be placed away from the curb and gutter, street, sidewalk, and private property immediately to eliminate hazards to the motoring public and pedestrians and to eliminate damage to private property. The Contractor shall also remove and dispose of any flags left by utility companies responding to J.U.L.I.E. locate requests. Disposal of Grinding debris generated by work described in this contract shall be the responsibility of the Contractor.

### AUTHORIZATION & SIGNATURE

*I have reviewed this documents and agree to fully comply with all specifications herein.*

Company Name: Winkler Tree Center

Name of Authorized Signee: Patrick Leatherman

Signature of Authorized Signee: Patrick Leatherman

Title: District Manager Date: 9-12-25