



Village of Orland Park
14700 Ravinia Avenue
Orland Park, Illinois 60462
ATTN: John Ingram

Office #708-403-6350

September 3, 2009

JOB: Sewer Repair
7919 Sycamore Drive
15165 Primrose Lane

PROPOSAL

Proposal to repair a sewer in Orland Park as follows:

7919 Sycamore Drive

- Expose existing sanitary sewer main on west side of Primrose Lane, approximately 12' deep
- Replace existing 6" clay tile sewer stub with new 6" ABS S.D.R. 23.5 pipe from sewer main to property line, 1' west of sidewalk
- No clean out tee on sewer service
- Park Plumbing to provide ditch box/shoring, as required
- Remove (2) sections of public walk
- Remove clay tile hub from sewer main, install new Fernco tapping saddle

15165 Primrose Lane

- Replace existing 6" clay tile sewer service, with new 6" ABS S.D.R. 23.5 pipe from main to "curb line" of Primrose Lane
- No cleanout tee, curb removal or street cut for this stub
- Remove clay tile hub from sewer main, install new Fernco tapping saddle
- Bed all new excavation with ¾" stone, trench backfill at sidewalk cut

EXCLUSIONS

- No permit fee included in this proposal
- Village of Orland Park to provide all ¾" stone for backfill
- Village of Orland Park shall provide dump truck and driver for removal of spoil from site, trucks shall be loaded by Park Plumbing employees and equipment
- Village of Orland Park supplied material, trucks and driver – must be provided at an "on time" basis
- No ground repair or sidewalk replacement included in this proposal

15556 S. 70th Court
Orland Park, IL 60462



(708) 429-2811
Fax (708) 429-2854

We hereby propose to furnish material and labor in complete accordance with the above specifications for the sum of:

Six Thousand Three Hundred Fifty Dollars and 00/100 -----\$6,350.00

Payment due in full upon completion of scope of work.

Authorized By: Thomas A. Peus Date: 09.03.09

Accepted By: _____ Date: _____
Park Plumbing, Inc. reserves the right to withdraw this proposal, if not accepted within 30 days.