

**Village of Orland Park****2025 Fall Tree Removal Project - Proposal Sheet**

All tree removals must be stump ground approximately 6-8" below grade level. All stump grindings must be hauled away to level grade. Contractors are responsible for all utility locates.

Contact Village Forester Georgie Szymczak with any questions:  
312-502-8655

**TREE REMOVALS**

| ADDRESS                              | JOB SITE NUMBER | NUMBER OF TREES TO BE REMOVED / STUMPED | DBH                          | COMMENTS                                                                                            |
|--------------------------------------|-----------------|-----------------------------------------|------------------------------|-----------------------------------------------------------------------------------------------------|
| 14955 El Cameno Real Drive           | #15             | 1                                       | 23"                          | Silver Maple                                                                                        |
| West of Ravinia Ave and 151st Street | #17             | 10                                      | Various (Small DBH)          | Crabapples Under <b>Powerlines</b> Across from Police Department on 151st St (North Side of Street) |
| 7425 Tiffany Dr                      | #6              | 1                                       | 24"                          | Cottonwood                                                                                          |
| 9155 Brookside Court                 | #5              | 1                                       | 20"                          | Pear Tree Along Pond Shoreline, West of House                                                       |
| 15412 Primrose Court                 | #8              | 1                                       | 30"                          | Silver Maple                                                                                        |
| 15365 Orchid Court                   | #7              | 1                                       | 29"                          | Silver Maple                                                                                        |
| 8509 Hemlock Street                  | #11             | 1                                       | 26"                          | Silver Maple                                                                                        |
| 8320 Sunset Ridge Court              | #9              | 4                                       | 26,27,29,39"                 | All Silver Maples                                                                                   |
| 8554 Fir Street                      | #13             | 1                                       | 26"                          | Silver Maple                                                                                        |
| 8546 Fir Street                      | #12             | 1                                       | 40"                          | Silver Maple                                                                                        |
| 9316 Birch Street                    | #4              | 1                                       | 27"                          | Silver Maple                                                                                        |
| 14517 Woodland Avenue                | #1              | 1                                       | 25"                          | Oak (far west closest to street)                                                                    |
| 8401 Golfview Drive                  | #10             | 5                                       | 20,20,21,21,21"              | All Ash                                                                                             |
| 8919 147th Street                    | #18             | 3                                       | 21,23,26"                    | All Silver Maples                                                                                   |
| 14671 West Avenue                    | #3              | 1                                       | 25"                          | White Oak (in greenspace north of building)                                                         |
| 14700 Park Lane                      | #2              | 1                                       | 21"                          | Burr Oak (in frisbee golf course)                                                                   |
| 9110 Caddy Court                     | #14             | 1                                       | 36"                          | Silver Maple                                                                                        |
| 15249 Huntington Court               | #16             | 4                                       | 19" (HL), 11,14,14" (RM)     | Honey Locust and Red Maple near <b>Powerlines</b>                                                   |
| 8200 Eynsford Drive                  | #17             | 6                                       | 16,18,19,19,20" (L), 21"(CA) | Linden and Crabapple                                                                                |
| 13701 92nd Avenue                    | #20             | 1                                       | 25"                          | Siberian Elm                                                                                        |
| 10701 Churchill Drive                | #21             | 4                                       | 7,7,24,31"                   | All Elms                                                                                            |
| <b>LUMP SUM TREE REMOVAL PRICE</b>   | \$ 36,900.00    | <b>50</b>                               |                              |                                                                                                     |

**AUTHORIZATION & SIGNATURE**

Company Name: \_\_\_\_\_ SMITTYS TREE SERVICE \_\_\_\_\_

Name of Authorized Signee: \_\_\_\_\_ CHAZ SCHUTT \_\_\_\_\_

Signature of Authorized Signee: \_\_\_\_\_ CHAZSCHUTT \_\_\_\_\_

Title: \_\_\_\_\_ SALES MANAGER \_\_\_\_\_ Date: \_\_\_\_\_ 9/11/2025 \_\_\_\_\_

## Village of Orland Park Tree Removal Specifications

### A. GENERAL REQUIREMENTS

#### 1. Advance Notice to Village by Contractor

The Contractor shall notify via email the Operations Manager or the Consulting Municipal Arborist

representative prior to beginning work each day on this contract. The Contractor shall provide

weekly updates on the progress of all work. Following the completion of all work, the Contractor

inform the Village that the project is complete.

#### 2. Advance Notice to Residents by Contractor

The Contractor shall post suitable advance notice signs (at least 24 hours but not more than 2 days

prior to performing work in that location) on streets scheduled to be pruned. Signs are to be posted

in both parkways, at intersection corners, and suitable intervals, facing all directions of travel on

highways with signage provided by the Village of Orland Park. The Contractor, immediately upon

completion of work on each street, shall remove all such signs. The sign used must indicate the type

of work that is planned for the area (i.e. pruning), the date range it is planned for, and any other

language approved/required by the Municipality. The Contractor is responsible for all advance notice

to residents and this item is incidental to the cost of the overall contract work.

#### 3. Timeframes and Completion Requirements

The Contractor shall provide the Village with a proposed project schedule within (10) days of the

purchase order being issued. All work shall be completed by December 1, 2024, unless otherwise

approved by the Operations Manager.

#### 4. Site Appearance and Clean-Up

Tree removals and/or pruned limbs and branches temporarily placed in the parkway area shall be

placed in such a manner as to eliminate any obstruction to motor vehicles and pedestrians including

streets, driveways and sidewalks. At all times, pruning crews shall not advance more than 1 block

ahead of chipping/clean-up crews.

The Contractor shall clean up the site and remove and dispose of all debris. Site cleanup shall include

removal of sawdust, small twigs, chips, leaves, trunks and limbs from the street, curb, parkway,

sidewalk, private lawns and driveways with the appropriate tools for the job. The site shall be

returned to the same state it existed in prior to the pruning work. Under no circumstances shall any

materials be allowed to lie on the parkway overnight.

As pruning may occur during or after snow events, some debris may filter down through the snow

and may not be immediately accessible for clean-up. In these instances, it is the responsibility of the

Contractor to re-clean and rake up debris in these areas within 2 to 3 days after the snow melts. No

extra payment shall be made for this clean-up work.

#### 5. Protection of Property

The Contractor shall take all necessary precautions to eliminate damage to adjacent trees and shrubs,

lawns, curbs, walks, or other real or personal property. Holes made in lawns, regardless of size, shall

be filled with black dirt and seeded with a turf grass lawn seed mix. Any damage shall be rectified

within ten (10) days. Equipment shall not enter upon private property unless the property owner(s)

consent or the Operations Manager.

## 6. Damage to Public or Private Property

Should any damage to private or public property occur because of the service performed or work

done by the Contractor, the Contractor shall immediately notify the Operations Manager, the

Consulting Municipal Arborist, or other Village representative of such damage. Any correction of

damage shall be resolved within ten (10) days after damage occurs. Should the damage not be

rectified within the period agreed upon or to the satisfaction of the Operations Manager, the Village

reserves the right to repair or replace that which was damaged and assess the Contractor such costs

as may be reasonable and related to damage caused by the Contractor and deduct these costs from

any payment due the Contractor.

## 7. Contractor Personnel and Equipment

The Contractor shall supply all material, equipment, and personnel necessary to complete the work

specified. The Contractor shall rent equipment as needed to cover any equipment breakdowns that

would cause this contract to not be completed in the allotted time. All vehicles and equipment shall

have the Contractor's name in a visible location. All vehicles and equipment shall abide by the

standards listed in the Traffic Control section. All vehicles and equipment shall have the appropriate

items to avoid damage to public and private property (example – boards or pads for outriggers to

avoid depressions, etc.)

The Contractor shall employ only competent and efficient employees. All employees and supervisors

shall wear uniforms or apparel clearly displaying the company name for ease of identification. All

individuals shall be familiar with the removal specifications. The Operations Manager or other Village

representative shall have, throughout the life of the contract, the right of reasonable rejection and

approval of staff assigned to the work by the Contractor. If the Operations Manager, Consulting

Municipal Arborist or other Village representative rejects staff, the Contractor must provide replacement staff satisfactory to the Operations Manager or other Village representative in a timely

manner and at no additional cost to the Village. The day-to-day supervision and control of the

Contractor's employees is the responsibility solely of the Contractor.

The Contractor shall always endeavor to maintain good relations with the public and respectfully

answer questions. If work and equipment must block a driveway, the Contractor shall contact the

property resident to inform them of the work, shall keep the time of blockage to a minimum and

shall move equipment promptly if requested.

#### 8. Work Crew Supervision

The Contractor shall always provide qualified supervision of each crew while working under this

contract. Each supervisor shall be fluent in English and be authorized by the Contractor to accept

and act upon all directives issued by the Operations Manager or other Village representative.

#### 9. Workdays, Working Hours, and After-Hours Contact

The Contractor shall schedule work between the hours of 7:30 a.m. and 4:00 p.m., Monday through

Friday, unless authorized by the Operations Manager or another Village representative. Any work

within a two-block radius of a school shall be performed between the hours of 9:00 a.m. and 2:00

p.m. It is preferred that work is scheduled on days when school is not in session. Any work along a

street with significant traffic during rush-hours shall be performed between the hours of 9:00 a.m.

and 4:00 p.m.

#### 10. Safety Standards

All equipment to be used and all work to be performed shall be in full compliance with the most

current revision of the ANSI Z133.1-2012 Safety Requirements for Arboricultural Operations, or as

amended. Contractor personnel exposed to public vehicular traffic shall wear warning vests or other

suitable garments marked with or made of reflectorized material. At a minimum, this includes ANSI

Class 2 garments.

#### 11. Traffic Control

The Contractor shall conduct its operations in a manner that will not interrupt pedestrian or vehicle

traffic except as approved by the Village. The work area shall be confined to the smallest area

possible to allow maximum use of the street or sidewalk and to minimize any hazard to traffic or

pedestrians. The Contractor shall provide adequate traffic control for work area protection in

compliance with the Federal Highway Administration Manual on Uniform Traffic Control Devices for

Streets and Highways (MUTCD) current edition, the State of Illinois Illinois Vehicle Code, the Illinois

Department of Transportation Highway Standards, and the Illinois Department of Transportation

Handbook of Traffic Engineering Practice for Small Cities. All personnel, signs, barricades, and any

other items or devices necessary shall be provided by the Contractor. The Village shall make no

separate payment for this work. Traffic control shall include but not be limited to the following:

1. All work vehicles shall be positioned on the same side of the street as the work site.
2. Whenever possible the work site on a two-lane street or highway shall be confined to one traffic lane leaving the opposite lane open to traffic.
3. Work area protection shall consider the duration of the project, the size of the project, the lanes

of traffic, the volume of traffic, the speed limit, and the distance to the work area from the pavement.

4. Work vehicles shall have the flasher light lit but not as a substitute for any traffic control devices

for work area protection that may be necessary.

5. Under certain field conditions such as hills and curves, the spacing of the traffic control devices

shall be adjusted as necessary.

6. Warning signs such as "Men Working" shall be diamond shaped having a black symbol or message

on an orange reflective background. Such signs shall have a minimum size of 36 inches by 36 inches

with a maximum size of 48 inches by 48 inches. Such signs shall be posted at a minimum height of 12

inches above the pavement.

7. Cones used as daytime channeling devices shall be at least 18 inches tall, conical or tubular in

shape with a broadened base, and orange in color. Cones shall be spaced equal in feet to the posted

speed limit or closer along the taper length.

8. Channeling devices such as cones shall be positioned to provide adequate taper length before

the work area to guide traffic through the work area. Tapers approaching the work zone shall be:

- \* 150' minimum for posted speed limits 35 mph or higher

- \* 50' minimum for posted speed limits 30 mph or less

9. Should individuals progress ahead of vehicles, such as tree climbers, cones shall be placed in the

roadway to alert motorists of activity in those trees.

10. For lane closures on busy streets, appropriate signal boards and warning signs such as "Right Lane

Closed" and channeling devices at the appropriate intervals shall be used depending on the speed

limit.

11. Should complete street closure be required to complete contract work, the Contractor shall

notify the Public Works Department to coordinate and to plan appropriate actions. At the time the

road is closed, the Contractor shall use appropriate barricades (at least 3 Type II barricades at each

intersection), and "Road Closed" and "Detour" arrow signs shall be used to direct traffic around the

work area.

12. Flaggers shall be appropriately dressed (orange vest, etc.) to alert motorists, shall stand in a

conspicuous position facing approaching traffic, and shall use the proper traffic control sign and IDOT

flagging procedures when directing traffic.

12. Inspection of Work

All work shall be completed to the satisfaction of the Operations Manager or the Consulting Municipal Arborist and same shall resolve any questions as to proper procedures or quality of

workmanship.

13. Unsatisfactory or Unsafe Work

If, at any time during the contract, the service performed, or work done by the Contractor is considered by the Village to create a condition that threatens the health, safety, or welfare of the

community, the Contractor shall, on being notified either by written or oral notice, immediately

correct such deficient service or work. In the event the Contractor fails, after notice, to correct the

deficient service or work immediately, the Village shall have the right to order correction of the

deficiency by separate contract or with its own resources at the expense of the Contractor. The

Village reserves the right to terminate the whole or any part of this contract in the event the awarded Contractor fails to perform any of the provisions of this contract.

#### 14. Utility Locates

Contractors are responsible for all utility locates.

### B. TREE REMOVAL WORK

#### 1. Tree Removal

The Contractor shall remove all trees designated for removal by the Orland Park Operations Manager or

Consulting Municipal Arborist. Removal shall consist of cutting down each tree in a safe manner to a

point four inches above the adjacent ground level. Stumps shall be flush and level without pointed wood

fibers projecting upward. The Contractor shall remove and dispose of all tree limbs and tree trunks from

the site in accordance with applicable ordinances and regulations of the Village of Orland Park, Cook

County, and the State of Illinois. The Contractor shall use caution and good judgment during tree

removal operations particularly when deciding if it may be appropriate to "flop" a tree, or how to make

the final trunk cut of a "limbed" tree. Sidewalks, curbs, streets, and utility access hole structures shall

always be protected from the impact of falling wood by use of the tree or limb ground supports. Ropes

or other mechanical devices shall be used to lower all limbs of sufficient size that may cause damage to

other trees or surrounding public or private property.

## 2. Wildlife Considerations

Except for infectious diseased trees or structurally hazardous trees, should the Contractor discover a tree

marked for removal has interesting wildlife such as owls or songbirds or any birds protected by the

Migratory Bird Treaty Act, the trees are to be "limbed" out to ensure public safety and the Operations

Manager notified. Forestry staff will coordinate any public relations. The remaining stem or trunk shall

be removed later once wildlife has vacated the tree.

## C. STUMP REMOVAL AND RESTORATION WORK

### 1. Stump Removal

The Contractor shall remove all tree stumps and buttress roots designated by the Operations Manager

or Forestry representative to a point approximately eight inches (8") below the adjacent ground level.

Additionally, the Contractor shall remove all surface and sufficient subsurface roots as may be necessary

to eliminate "humps" in the lawn area adjacent to the stump.

### 2. Site Appearance and Disposal of Stump Grindings

After the grinding (removal) of a tree stump and all associated roots has been completed, Contractor

shall remove all stump grindings and associated debris from the site with the appropriate tools for the

job within 24 Hours. Grindings, and debris shall be placed away from the curb and gutter, street,

sidewalk, and private property immediately to eliminate hazards to the motoring public and pedestrians

and to eliminate damage to private property. The Contractor shall also remove and dispose of any flags

left by utility companies responding to J.U.L.I.E. locate requests. Disposal of Grinding debris generated

by work described in this contract shall be the responsibility of the Contractor.

#### AUTHORIZATION & SIGNATURE

I have reviewed this documents and agree to fully comply with all specifications herein.

Company Name: **SMITTYS TREE SERVICE**

Name of Authorized Signee: **CHAZ SCHUTT**

Signature of Authorized Signee: **CHAZ SCHUTT**

Title: **SALES MANAGER** Date: **9/11/2025**