

Kristo Lane & Dorstep Lane Construction Cost Estimate

Overall Total						Kristo Lane 480 L.F. 1440 S.Y.		Dorstep Lane 860 L.F. 2580 S.Y.		
No.	IDOT	Item	Quantity	Unit	Unit Price	Amount				
1	42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	120	SQ FT	\$4.75	\$570.00	120	\$570.00	0	\$0.00
2	42400800*	DETECTABLE WARNINGS	20	SQ FT	\$31.50	\$630.00	20	\$630.00	0	\$0.00
3	44000600	SIDEWALK REMOVAL	0	SQ FT	\$1.00	\$0.00	0	\$0.00	0	\$0.00
4	60608300	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-2.12	242	FOOT	\$18.25	\$4,416.50	65	\$1,186.25	177	\$3,230.25
5	60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	0	FOOT	\$20.50	\$0.00	0	\$0.00	0	\$0.00
6	44000500	COMBINATION CURB AND GUTTER REMOVAL	242	FOOT	\$4.25	\$1,028.50	65	\$276.25	177	\$752.25
7	*	CONCRETE SLAB RAISING	0	SQ FT	\$2.25	\$0.00	0	\$0.00	0	\$0.00
8	XX006395*	SHOTCRETE CURB & GUTTER REPAIR	40	FOOT	\$35.00	\$1,400.00	20	\$700.00	20	\$700.00
9	*	P.C.C. DRIVEWAY REMOVAL & REPLACEMENT, 5"	0	SQ FT	\$5.50	\$0.00	0	\$0.00	0	\$0.00
10	*	H.M.A. DRIVEWAY REMOVAL & REPLACEMENT, 3"	0	SQ YD	\$39.00	\$0.00	0	\$0.00	0	\$0.00
11	*	BRICK DRIVEWAY REMOVAL & REPLACEMENT	40	SQ FT	\$15.00	\$600.00	0	\$0.00	40	\$600.00
12	*	IMPRINTED COLORED PCC DRIVEWAY REMOVAL & REPLACEMENT	0	SQ FT	\$11.00	\$0.00	0	\$0.00	0	\$0.00
13	*	IMPRINTED COLORED HMA DRIVEWAY REMOVAL & REPLACEMENT	0	SQ YD	\$150.00	\$0.00	0	\$0.00	0	\$0.00
14	X0326806*	WASHOUT BASIN	1	EACH	\$400.00	\$400.00	0.5	\$200.00	0.5	\$200.00
15	20200100*	EARTH EXCAVATION	5	CU YD	\$20.00	\$100.00	5	\$100.00	0	\$0.00
16	44000167	HOT-MIX ASPHALT SURFACE REMOVAL, 4 1/2"	0	SQ YD	\$2.50	\$0.00	0	\$0.00	0	\$0.00
17	44000156	HOT-MIX ASPHALT SURFACE REMOVAL, 1 3/4"	0	SQ YD	\$1.40	\$0.00	0	\$0.00	0	\$0.00
18	40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	40	SQ YD	\$0.01	\$0.40	40	\$0.40	0	\$0.00
19		HOT-MIX ASPHALT SURFACE REMOVAL, EDGE MILL	8,100	SQ YD	\$1.75	\$14,175.00	6750	\$11,812.50	1350	\$2,362.50
20	40600100	HOT-MIX ASPHALT - PRIME COAT (BDE)	410	GALLON	\$0.01	\$4.10	150	\$1.50	260	\$2.60
21	*	CLASS D PATCHES- VARIOUS TYPES	150	TON	\$80.00	\$12,000.00	30	\$2,400.00	120	\$9,600.00
22	*	CLASS D PATCHES- VARIOUS TYPES- OFFSITE	0	TON	\$142.00	\$0.00	0	\$0.00	0	\$0.00
23	35101400*	AGGREGATE BASE COURSE, TYPE B	0	TON	\$13.00	\$0.00	0	\$0.00	0	\$0.00
24	35800100	PREPARATION OF BASE	0	SQ YD	\$0.85	\$0.00	0	\$0.00	0	\$0.00
25	35800200	AGGREGATE BASE REPAIR	0	TON	\$20.00	\$0.00	0	\$0.00	0	\$0.00
26	40201000*	AGGREGATE FOR TEMPORARY ACCESS	0	TON	\$17.00	\$0.00	0	\$0.00	0	\$0.00
27	20800150*	TRENCH BACKFILL, CA-6	10	TON	\$18.00	\$180.00	0	\$0.00	10	\$180.00
28	20800150*	TRENCH BACKFILL, CA-7	10	TON	\$24.00	\$240.00	0	\$0.00	10	\$240.00
29	40600825	POLYMERIZED LEVELING BINDER (MACHINE METHOD), N50	200	TON	\$79.00	\$15,800.00	70	\$5,530.00	130	\$10,270.00
30	40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	0	TON	\$53.73	\$0.00	0	\$0.00	0	\$0.00
31	40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	355	TON	\$57.50	\$20,412.50	130	\$7,475.00	225	\$12,937.50
32	25000110*	SEEDING, CLASS 1A (& TOPSOIL)	20	SQ YD	\$4.20	\$84.00	5	\$21.00	15	\$63.00
33	25100630	EROSION CONTROL BLANKET	20	SQ YD	\$5.25	\$105.00	5	\$26.25	15	\$78.75
34	25200100*	SODDING (& TOPSOIL)	0	SQ YD	\$18.00	\$0.00	0	\$0.00	0	\$0.00
35	28000510	INLET FILTERS	4	EACH	\$0.01	\$0.04	2	\$0.02	2	\$0.02
36	60109520*	PIPE UNDERDRAINS FABRIC LINED TRENCH, 6"	150	FOOT	\$16.00	\$2,400.00	0	\$0.00	150	\$2,400.00
37	550B0330*	STORM SEWERS, CLASS B, TYPE 2 10"	0	FOOT	\$30.00	\$0.00	0	\$0.00	0	\$0.00
38	60207005*	CATCH BASINS, TYPE C, FRAME & LID	0	EACH	\$1,675.00	\$0.00	0	\$0.00	0	\$0.00
39	60300305*	FRAMES AND LIDS TO BE ADJUSTED (STEEL RING)	0	EACH	\$150.00	\$0.00	0	\$0.00	0	\$0.00
40	60255500*	MANHOLES TO BE ADJUSTED	1	EACH	\$280.00	\$280.00	0	\$0.00	1	\$280.00
41	60257900*	MANHOLES TO BE RECONSTRUCTED, BLOCK	0	EACH	\$900.00	\$0.00	0	\$0.00	0	\$0.00
42	60257900*	MANHOLES TO BE RECONSTRUCTED, CONE SECTION	0	EACH	\$900.00	\$0.00	0	\$0.00	0	\$0.00
43	60257900*	MANHOLES TO BE RECONSTRUCTED, FLAT SLAB TOP	0	EACH	\$1,000.00	\$0.00	0	\$0.00	0	\$0.00
44	*	MANHOLE TO BE MORTARED	4	EACH	\$65.00	\$260.00	1	\$65.00	3	\$195.00
45	88600100	DETECTOR LOOP, TYPE I	0	FOOT	\$20.00	\$0.00	0	\$0.00	0	\$0.00
46	*	TRAFFIC CONTROL AND PROTECTION, SPECIAL	0	LSUM	\$35,000.00	\$0.00	0	\$0.00	0	\$0.00
47	78000100	THERMOPLASTIC PAVEMENT MARKING- LETTERS & SYMBOLS	0	SQ FT	\$6.60	\$0.00	0	\$0.00	0	\$0.00
48	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	0	FOOT	\$0.66	\$0.00	0	\$0.00	0	\$0.00
49	78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	54	FOOT	\$0.91	\$49.14	54	\$49.14	0	\$0.00
50	78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	40	FOOT	\$2.00	\$80.00	40	\$80.00	0	\$0.00
51	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	28	FOOT	\$4.40	\$123.20	28	\$123.20	0	\$0.00

\$75,338.38

\$31,246.51

\$44,091.87