

FLOORS, INCORPORATED

1341 COBBLESTONE WAY
P.O. BOX 700
WOODSTOCK, IL 60098-0700
(815) 338-6566
Fax (815) 338-6679

Date: January 10, 2025

To: Village of Orland Park

Re: Wood floor refinishing
Pricing per Sourcewell contract #031022-RBI

PROPOSAL

We Propose to:

New Dance Room (Studio B) – approx. 1,275 sq. ft. total:

Machine sand the existing maple floor, apply 2 coats water-based polyurethane floor sealer and apply 2 coats water-based polyurethane floor finish.

FOR THE SUM OF - - - \$7,950.00
(Seven thousand nine hundred fifty and 00/100 Dollars)

Notes: We require 220 volt/3 phase power and hook-up for our sanders. If this is not available we will bill for the added cost.

All above prices are subject to change after thirty days

Respectfully submitted by: _____ Steve Fantuzzi

FLOORS, INCORPORATED

1341 COBBLESTONE WAY
P.O. BOX 700
WOODSTOCK, IL 60098-0700
(815) 338-6566
Fax (815) 338-6679

Date: January 10, 2025

To: Village of Orland Park

Re: FLC
Wood floor re-coat work
Pricing per Sourcewell contract #031022 - RBI

PROPOSAL

We Propose to:

Dance Room (Studio A) – approx. 1,023 sq. ft.:

Prep/Screen the existing maple flooring and apply 2 coats water based polyurethane floor finish.

FOR THE SUM OF - - - \$1,560.00
(One thousand five hundred sixty and 00/100 Dollars)

Notes: Owner to remove tape from the wood flooring and all equipment out of the room prior to the above work. Any time spent by Floors Incorporated to remove tape or equipment will be added to the final billing.

All above prices are subject to change after thirty days

Respectfully submitted by: _____ Steve Fantuzzi

FLOORS, INCORPORATED

1341 COBBLESTONE WAY
P.O. BOX 700
WOODSTOCK, IL 60098-0700
(815) 338-6566
Fax (815) 338-6679

Date: January 10, 2025

To: Village of Orland Park

Re: Orland Park Health and Fitness
Wood floor re-coat work
Pricing per Sourcewell contract #031022 - RBI

PROPOSAL

We Propose to:

Gymnasium, Studios A and B – approx. 9,000 sq. ft.:

Paint 2 pickleball courts on the wood gym floor. Prep/Screen the existing maple flooring and apply 2 coats water based polyurethane floor finish.

FOR THE SUM OF - - - \$15,140.00
(Fifteen thousand one hundred forty and 00/100 Dollars)

Notes: Owner to remove tape from the wood flooring and all equipment out of the room prior to the above work. Any time spent by Floors Incorporated to remove tape or equipment will be added to the final billing.

All above prices are subject to change after thirty days

Respectfully submitted by: _____ Steve Fantuzzi

FLOORS, INCORPORATED

1341 COBBLESTONE WAY
P.O. BOX 700
WOODSTOCK, IL 60098-0700
(815) 338-6566
Fax (815) 338-6679

Date: January 10, 2025

To: Village of Orland Park

Re: Sportsplex
Wood floor re-coat work
Pricing per Sourcwell contract #031022 - RBI

PROPOSAL

We Propose to:

Gymnasium – approx. 21,700 sq. ft.:

Prep/Screen the existing maple flooring and apply 1 coat oil based polyurethane floor finish.

FOR THE SUM OF - - - \$14,840.00
(Fourteen thousand eight hundred forty and 00/100 Dollars)

Notes: Owner to remove tape from the wood flooring and all equipment out of the room prior to the above work. Any time spent by Floors Incorporated to remove tape or equipment will be added to the final billing.

All above prices are subject to change after thirty days

Respectfully submitted by: _____ Steve Fantuzzi