



Henderson Products - Illinois
11921 Smith Drive
Huntley, IL. 61042

Toll Free: 888-360-7483
Office: 847-836-4996

Quote

Date: **4/6/18**
To: **Tom Morgan @ V/O Orland Park**
By: **Joe Vagle**
Re: **One Ton's 2018**

Henderson Truck Equipment-Illinois is pleased to quote the following equipment:

NJPA Number 58,277
Henderson Products NJPA Number 080114-HPI

(1) Henderson Mark III dump body

8' x 13" dump body made of 201 stainless steel
Fixed sides
Tapered 50" headsheet
3/16" AR400 floor
Telescopic double acting hoist
18" tall quick release tailgate w/ (1) 6" oblong hole in each rear corner post
One sets of LED S/T/T/BU combination lights, one installed in each rear corner posts
Re-install factory S/T/T lights on outside of chassis rails at rear

No window cut outs in front headsheet of body

Body up light w/ proximity switch
Whelen LED beacon installed in self leveling bracket above cabshield lightbox on drivers side
Cabshield lightboxes installed, one in each front corner with the following lights installed
Two Whelen 6" oval LED amber warning lights facing the side, one per side
Two Whelen 6" oval LED amber warning lights facing the rear, one per side
Two Grote 6" oval LED red S/T/T lights facing the rear, one per side

Utilize Ford Upfitter switches as follows

Switch one - Pump
Switch two - Front strobe
Switch three - Rear and top strobe
Switch four - Spreader light
Switch five - Auxillary
Switch six - Auxillary

One set of full poly fenders installed over rear wheels
Additional mudflaps are not required

FOR COAL CHUTE, ADD \$454.00 TO PRICE BELOW

(1) Central Hydraulic System

12 gallon **stainless steel** frame mounted reservoir/valve enclosure combination
Force America clutch pump system installed under the hood
Force America electric joystick controller
SSC5100EX spreader controller
One dual axis joystick to operate plow and dump
12 switches installed in spreader controller
Spreader quick disconnects installed in brackets below dump body floor - auger one side, spinner one side
Install Precise AVL equipment in cab

Spreader circuit plumbed with stainless steel hydraulic tubing
Hydraulic fluid, hose, fittings, and quick disconnects as required
install joystick console in center console - see pictures of 2016 builds
install spreader controller off joystick console, passenger side

(1) Trailer Towing Package

5/8" pintle plate
2" receiver tube
8 ton 2-5/16" pintle ball combo
6 pole trailer plug
Back up Alarm

(1) Henderson Under-Tailgate Salt Spreader

Spreader to be made of grade 50 mild steel
5:1 gearbox drive with internal speed sensor
Old Style Full Opening Bottom Clean Out Door
Poly spinner disc
Mounting hardware
Powder coat painted orange
Install spreader light on spreader endplate drivers side

(1) Fisher HD2 Snowplow

9' long
Plumbed for central hydraulics
Rubber snow deflector
Carbide cutting edge
Quick couplers installed in front bumper
Bulkhead mount quick couplers in front bumper drivers side

Price per Unit:	\$36,655.00
Number of Units	2
Extended Price	\$73,310.00
Tax	
Total Quote Price	\$73,310.00

FOB Huntley, IL

Please note the following regarding installation quotes:

A clean truck frame without obstruction is assumed in the pricing of our quote. Re-positioning of air tanks, fuel tanks or other obstacles to the ease of installation may require additional charges. Henderson will notify you before modification if this occurs.