



9550 W. 55th Street • Suite A • McCook, IL 60525 • 708-588-2500 • 708-588-2501 Fax

**153RD STREET & RAVINIA  
 TEMPORARY TRAFFIC SIGNAL INSTALLATION  
 ORLAND PARK**

ITEM DESCRIPTION =====	QUANTITY =====	UNIT ===	UNIT PRICE \$\$\$ US =====	ITEM AMOUNT \$\$\$ US =====
---------------------------	-------------------	-------------	----------------------------------	-----------------------------------

**ALT BID 2**

45' WOOD POLE INSTALL ONLY	4	EACH	\$ 1,235.00	\$ 4,940.00
POLE MOUNTED SERVICE INSTALL ONLY	1	EACH	\$ 1,689.00	\$ 1,689.00
FULL ACTUATED CONTROLLER AND TYPE 4 CABINET INSTALL ONLY	1	EACH	\$ 2,367.00	\$ 2,367.00
SH LED 1 FACE 3 SEC SPAN WIRE MOUNT F&I	4	EACH	\$ 750.00	\$ 3,000.00
SH LED 1 FACE 5 SEC SPAN WIRE MOUNT F&I	8	EACH	\$ 1,175.25	\$ 9,402.00
PED SH LED 2 FACE BM W/ CD F&I	4	EACH	\$ 636.50	\$ 2,546.00
PED PUSH BUTTON NON LATCHING TYPE	4	EACH	\$ 340.50	\$ 1,362.00
GUY WIRE, MESSANGER WIRE, SIGNAL CABLE AS NEEDED	1	LSUM	\$ 6,138.00	\$ 6,138.00
CONDUIT IN GROUND 1" UNIT DUCT	746	FOOT	\$ 11.49	\$ 8,571.54
LOOP DETECTOR TYPE 1	657	FOOT	\$ 17.68	\$ 11,615.76
MODIFY EXISTING FAC & TYPE IV CABINET	1	LSUM	\$ 1,498.00	\$ 1,498.00
TRAFFIC CONTROL AND PROTECTION	1	LSUM	\$ 1,575.00	\$ 1,575.00

\$ 54,704.30