

Bill To

Doug Medland Village of Orland Park Public Works Dept 14544 D Ravinia Avemir Orland Park IL 60462

2805 E. Plano Pkwy, Suite 200 Plano, Texas 75074

ISO 9001:2008 Certified

GSA Schedules: IT 70, 71 Furniture and 81B Shipping Cases

Ship To

Doug Medland Village of Orland Park Public Works Dept 14544 D Ravinia Avemir Orland Park IL 60462

Quote No. QUO00204737

Date 8/3/2012 Acct. No. CUS00014794 Expires 11/9/2012 **Point of Contact** Doug Medland **Installation Date** 11/2/2012 PO#

Terms

Net 30 **Shipping Method**

FOB

Origin **Delivery Services** Dock

Rep Laura Viars

Line Item	Item	Description	Quantity	Price	Extended
		Rackmount Solutions, Inc. is classified as small business, woman owned. We qualify for the SBA-WOSB program as defined by Federal Acquisition Regulation (FAR) provision 52.212-3, 52.219-1 and 52.219.22. (Woman Owned Small Business Federal Contract Program) TEIN: 06-1703393 DUNS: 102181083 CAGE code: 1ZFZ0 Quote is valid for 30 days Payment: WAWF, net 30, government purchase card Shipping: Freight prepay and add.			
	Open Market	The item(s) below is an open market item.	1	0.00	0.00
	Custom	This is a custom product and cannot be returned. If order is cancelled during the manufacturing cycle, time and materials will be charged.	1	0.00	0.00
	Part No.	A772042ACRM10K3:	1	8,220.13	8,220.13
		Revision A, 9/10/12 (Upgrades Foam Package) 44U Rackmount AC Cabinet Assembly, 230VAC with 31U of usable rack space. 42" Usable Depth ***INCLUDES HOOD MOUNTED ON TOP OF ACU ***INCLUDES TEMP DISPLAY ON FRONT DOOR ***WITH CABLE ACCESS THRU BOTTOM PANEL ***FRONT & REAR DOORS ARE RH HINGED ***SIDES ARE INTERNALLY REMOVABLE ONLY			
		Overall Height: 84.58 Overall Width: 24.00 Overall Depth: 45.54			
		Consisting Of:			
		(1) 772042-LPatented Aluminum Extruded Welded Frame, Base, Casters, Levelers, (3) pair "L" Shaped REDUCER Rails to create a 19" Rack Mounting.			
		* (1) M6-40 Hardware Pack			



Quote No. QU000204737

 Date
 8/3/2012

 Acct. No.
 CUS00014794

Line Item	Item	Description	Quantity	Price	Extended
		(1) LD5720-2EL-RH Lexan Door w/ Aluminum Extruded Frame, Smoke-Gray Lexan, (2) Lockable Swing Handle (2) Female hinges (2) LD Catch bracket and mounting hardware. (This is a typical door size for a 33U Cabinet) *RH HINGED* ***ADD CUTOUT FOR MTEMP1000 DISPLAY***			
		(1) MTEMP1000 Temperature Display mounted in front door Lexan window at upper LH corner. Locate sensor at upper LH side near center of cab			
		(1) SD6420-2EL-RH Steel Rear Door with (2) Lockable Swing Handles (2) Female Hinges (2) SD Catch Brackets and mounting hardware (This is a typical door size for a 37U Cabinet) *RH HINGED*			
		(1) SP7742-IR Side Panels INTERNALLY Removable Priced per Pair			
		(1) MLB16-1026-G016 9U Rackmount Air-Conditioner -9,000 BTU -230V			
		(1) 101412 Front Cover with: (4) 1/4-20 x 1 1/2" Button Head Screws (4) 1/4-20 Spring Nuts			
		(1) MLB16-FRTCOVER Front Cover for 10K Rackmount Air Conditioner			
		(1) ACUHOODKIT-10 Hood Kit Assembly to direct cooled air from top of ACU toward the front of the equipment. Foam Tape (1/2 x 1 open cell) installed between hood and ACU)			
		(1) CAP20X-AC1 "L" Shaped Filler at top of AC unit for sealing. Mounts to outside of extrusion using screws and springnuts. For 20" wide cabinet only.			
		(1) CAP19-12-LB1642 7U Rear Lower A/ C Exit Panel Assembly for an LB16 style Air Conditioner in a 42" deep cabinet			



Quote No. QU000204737

 Date
 8/3/2012

 Acct. No.
 CUS00014794

Line Item	Item	Description	Quantity	Price	Extended
		(1) FS1924-3024" Fixed adjustable shelf that mounts to front and intermediate rails allowing the intermediate rails to be adjusted from 24" to 30". Shelf will support 200 lbs. evenly distributed and is made of 14 GA CRS			
		(1) ST2042Solid Top Panel			
		(1) SBP2042-CADSolid Bottom Panel with Cable Access Door			
		(1) GASKET-ACComplete sealing of front and rear doors, top and bottom panels using closed cell foam for AC cabinets. (Use Stockwell Adhesive Backed Foam)			
		(1) CP4048Cushion Pallet. This pallet has the IPPC stamp and is approved for International shipments.			
		Customer has opted out of using the recommended AC Duct Kit. Please monitor the temperatures of your equipment closely to ensure that there has been no recirculation of hot air into your cabinet.			
	Lead Time	Lead Time 4 to 5 weeks	1	0.00	0.00
	Shipping-Truck	Truck freight charges are prepay and add, FOB origin. Actual charges may vary slightly pending delivery conditions, fuel surcharges and/or additional services requested from the driver.	1	203.41	203.41
		PLEASE ADVISE YOUR SALES REP IF YOU DO NOT HAVE A DOCK HIGH OR A FORK LIFT.			
		This is for a Dock delivery. please let us know if you need lift gate truck, inside delivery, or both Thank you			
	Buy American	TAA Compliant. These items meet the FAR 52.225-2 Buy American Act and we will provide a certificate as requested.	1	0.00	0.00
	SBA-WOSB	Rackmount Solutions, Inc. qualifies for the SBA-WOSB program and is listed in CCR and ORCA. All documentation is on file with the SBA repository.	1	0.00	0.00
		Under the WOSB Program, contracting officers may restrict competition for Federal contracts to small business concerns owned and controlled by women, under certain conditions, including but not limited to: (1) The procurement requirement is in an industry the SBA			



Quote No. QU000204737

 Date
 8/3/2012

 Acct. No.
 CUS00014794

Line Item	Item	Description	Quantity	Price	Extended
		has determined to be underrepresented or substantially underrepresented by small business concerns owned and controlled by women.			
	Viars	Your account rep is Laura Viars. If you have product questions please call or email lviars@rackmountsolutions.net Tel: 866-207-6631 x336, Fax: 972-276-6484	1	0.00	0.00

Quoted prices do not include applicable taxes, insurance, shipping, delivery or set up fees unless specifically quoted above. All prices are subject to change without notice. ATTENTION: PLEASE READ BEFORE ACCEPTING THIS QUOTE. Accepting this quote confirms you have read and accept the policy terms and conditions and return policies of Rackmount Solutions as posted on our website: www.rackmountsolutions.net

Total \$8,423.54

